



**US Army Corps
of Engineers®**
Galveston District

<i>PROJECT INFO</i>	
PROJECT NAME & REACH	GULF INTRACOASTAL WATERWAY High Island to Rollover Pass
PROJECT DIMENSIONS	16' x 125'
LOCAL SPONSOR	TxDOT
PROJECT MANAGER	Ben Boren, 409-766-3833

<i>DESCRIPTION OF WORK</i>		<i>ENVIRONMENTAL RESTRICTIONS</i>	
DESC. OF WORK	Dredging and beach nourishment	DATES:	1-Mar-2006 TO 31-Aug-2006
EST. QUANTITY	1,000,000 cu. yds.	DESC:	Customer window and sea turtle window at Rollover Pass- must complete by 1-Mar-2006
TYPE OF DREDGE	Pipeline		

<i>PROPOSED DATES</i>			
ADVERTISE DATE	15-Dec-2005	START WORK	12-Feb-2006
OPEN BIDS	17-Jan-2006	DURATION	4 months

<i>SCOPE OF WORK</i>
<p>P&S currently under development. Updates will be provided</p> <p>*1 million CY of material to be dredged with hydraulic cutter head. Beach nourishment at Rollover Pass</p> <p>*Placement Areas: Confined: 28, 32, 33, 34, 35. Beach nourishment: Rollover Pass Beach (west side)</p> <p>*Levee repair: PA's 36, 38, 40 raise to required elevation with side cast material.</p> <p>*Drop outlet repair: PA'S 28, 34, 35 minor repairs</p> <p>*Longest Pump: ~8,500'. Also, Rollover Pass Beach nourishment will require approx. 8,000' of pipe.</p>

** This information is provided to help Contractor determine if work fits Contractor's capabilities and schedule. Information should not be relied upon to prepare bid documents.*

GIWW – High Island to Port Bolivar

