

**APPENDIX C**

**BIOLOGICAL ASSESSMENT FOR IMPACTS TO ENDANGERED AND  
THREATENED SPECIES RELATIVE TO THE NORTH PADRE ISLAND STORM  
DAMAGE REDUCTION AND ENVIRONMENTAL RESTORATION PROJECT,  
NUECES COUNTY, TEXAS**

BIOLOGICAL ASSESSMENT FOR IMPACTS TO  
ENDANGERED AND THREATENED SPECIES  
RELATIVE TO THE NORTH PADRE ISLAND  
STORM DAMAGE REDUCTION AND  
ENVIRONMENTAL RESTORATION PROJECT  
NUECES COUNTY, TEXAS

U.S. Army Corps of Engineers  
Galveston District  
2000 Fort Point Road  
Galveston, Texas 77550

June 2002

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
List of Figures	C-vi
List of Tables	C-vi
1.0 <u>INTRODUCTION</u>	1
1.1 PURPOSE OF THE BIOLOGICAL ASSESSMENT	1
1.2 DESCRIPTION OF THE PROPOSED ACTIONS	5
2.0 <u>IMPACT ASSESSMENT FOR LISTED SPECIES</u>	11
2.1 SOUTH TEXAS AMBROSIA	11
2.1.1 <u>Reasons for Status</u>	11
2.1.2 <u>Habitat</u>	11
2.1.3 <u>Range</u>	12
2.1.4 <u>Distribution in Texas</u>	12
2.1.5 <u>Presence in the Project Area</u>	12
2.1.6 <u>Effects of the Project</u>	12
2.2 BLACK LACE CACTUS	12
2.2.1 <u>Reasons for Status</u>	12
2.2.2 <u>Habitat</u>	13
2.2.3 <u>Range</u>	13
2.2.4 <u>Distribution in Texas</u>	13
2.2.5 <u>Presence in the Project Area</u>	13
2.2.6 <u>Effects of the Project</u>	13
2.3 SLENDER RUSH-PEA	13
2.3.1 <u>Reasons for Status</u>	13
2.3.2 <u>Habitat</u>	14
2.3.3 <u>Range</u>	14
2.3.4 <u>Distribution in Texas</u>	14
2.3.5 <u>Presence in the Project Area</u>	14
2.3.6 <u>Effects of the Project</u>	14
2.4 KEMP'S RIDLEY SEA TURTLE	14
2.4.1 <u>Reasons for Status</u>	14
2.4.2 <u>Habitat</u>	15
2.4.3 <u>Range</u>	16
2.4.4 <u>Distribution in Texas</u>	16
2.4.5 <u>Presence in the Project Area</u>	16
2.4.6 <u>Effects of the Project</u>	17
2.5 GREEN SEA TURTLE	17
2.5.1 <u>Reasons for Status</u>	17
2.5.2 <u>Habitat</u>	18

## TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
2.5.3	<u>Range</u>	18
2.5.4	<u>Distribution in Texas</u>	18
2.5.5	<u>Presence in the Project Area</u>	19
2.5.6	<u>Effects of the Project</u>	19
2.6	LOGGERHEAD SEA TURTLE	19
2.6.1	<u>Reasons for Status</u>	19
2.6.2	<u>Habitat</u>	20
2.6.3	<u>Range</u>	20
2.6.4	<u>Distribution in Texas</u>	20
2.6.5	<u>Presence in the Project Area</u>	21
2.6.6	<u>Effects of the Project</u>	21
2.7	HAWKSBILL SEA TURTLE	21
2.7.1	<u>Reasons for Status</u>	21
2.7.2	<u>Habitat</u>	21
2.7.3	<u>Range</u>	22
2.7.4	<u>Distribution in Texas</u>	22
2.7.5	<u>Presence in the Project Area</u>	22
2.7.6	<u>Effects of the Project</u>	23
2.8	LEATHERBACK SEA TURTLE	23
2.8.1	<u>Reasons for Status</u>	23
2.8.2	<u>Habitat</u>	23
2.8.3	<u>Range</u>	24
2.8.4	<u>Distribution in Texas</u>	24
2.8.5	<u>Presence in the Project Area</u>	24
2.8.6	<u>Effects of the Project</u>	24
2.9	BROWN PELICAN	25
2.9.1	<u>Reasons for Status</u>	25
2.9.2	<u>Habitat</u>	25
2.9.3	<u>Range</u>	25
2.9.4	<u>Distribution in Texas</u>	26
2.9.5	<u>Presence in the Project Area</u>	26
2.9.6	<u>Effects of the Project</u>	27
2.10	BALD EAGLE	27
2.10.1	<u>Reasons for Status</u>	27
2.10.2	<u>Habitat</u>	28
2.10.3	<u>Range</u>	28
2.10.4	<u>Distribution in Texas</u>	28
2.10.5	<u>Presence in the Project Area</u>	29

## TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
2.10.6	<u>Effects of the Project</u>	29
2.11	WHOOPING CRANE	29
2.11.1	<u>Reasons for Status</u>	29
2.11.2	<u>Habitat</u>	29
2.11.3	<u>Range</u>	30
2.11.4	<u>Distribution in Texas</u>	30
2.11.5	<u>Presence in the Project Area</u>	30
2.11.6	<u>Effects of the Project</u>	31
2.12	NORTHERN APLOMADO FALCON	31
2.12.1	<u>Reasons for Status</u>	31
2.12.2	<u>Habitat</u>	31
2.12.3	<u>Range</u>	31
2.12.4	<u>Distribution in Texas</u>	32
2.12.5	<u>Presence in the Project Area</u>	32
2.12.6	<u>Effects of the Project</u>	32
2.13	PIPING PLOVER	32
2.13.1	<u>Reasons for Status</u>	32
2.13.2	<u>Habitat</u>	33
2.13.3	<u>Range</u>	33
2.13.4	<u>Distribution in Texas</u>	33
2.13.5	<u>Presence in the Project Area</u>	34
2.13.6	<u>Effects of the Project</u>	34
2.14	MOUNTAIN PLOVER	37
2.14.1	<u>Reason for Status</u>	37
2.14.2	<u>Habitat</u>	38
2.14.3	<u>Range</u>	38
2.14.4	<u>Distribution in Texas</u>	38
2.14.5	<u>Presence in the Project Area</u>	39
2.14.6	<u>Effects of the Project</u>	39
2.15	ESKIMO CURLEW	39
2.15.1	<u>Reason for Status</u>	39
2.15.2	<u>Habitat</u>	40
2.15.3	<u>Range</u>	40
2.15.4	<u>Distribution in Texas</u>	40
2.15.5	<u>Presence in the Project Area</u>	41
2.15.6	<u>Effects of the Project</u>	41
2.16	OCELOT	41
2.16.1	<u>Reasons for Status</u>	41

## TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
2.16.2	<u>Habitat</u>	41
2.16.3	<u>Range</u>	42
2.16.4	<u>Distribution in Texas</u>	42
2.16.5	<u>Presence in the Project Area</u>	43
2.16.6	<u>Effects of the Project</u>	43
2.17	JAGUARUNDI	43
2.17.1	<u>Reasons for Status</u>	43
2.17.2	<u>Habitat</u>	43
2.17.3	<u>Range</u>	44
2.17.4	<u>Distribution in Texas</u>	44
2.17.5	<u>Presence in the Project Area</u>	45
2.17.6	<u>Effects of the Project</u>	45
2.18	WEST INDIAN MANATEE	45
2.18.1	<u>Reasons for Status</u>	45
2.18.2	<u>Habitat</u>	46
2.18.3	<u>Range</u>	46
2.18.4	<u>Distribution in Texas</u>	46
2.18.5	<u>Presence in the Project Area</u>	46
2.18.6	<u>Effects of the Project</u>	46
2.19	WHALES	47
3.0	<u>REFERENCES</u>	49

## LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	Project Location	3
2	Proposed Packery Channel and Placement Areas	7
3	Piping Plover Critical Habitat Units TX-6 and TX7	35

## LIST OF TABLES

<u>Table</u>		<u>Page</u>
1	Federally Endangered and Threatened Species of Potential Occurrence in the Packery Channel Project in Nueces County, Texas	2

## 1.0 INTRODUCTION

### 1.1 PURPOSE OF THE BIOLOGICAL ASSESSMENT

This Biological Assessment (BA) has been prepared for the purpose of fulfilling the U.S. Army Corps of Engineer's (USACE) requirements as outlined under Section 7(c) of the Endangered Species Act (ESA) of 1973 as amended. The proposed Federal action requiring the assessment is the construction of Packery Channel in Nueces County, Texas. Table 1 presents a list of Federally listed species addressed in this BA. For the purposes of this BA, the project area is defined as the construction footprint: the area where the actual dredging and construction will take place including the proposed placement areas. In the Draft Environmental Impact Statement (DEIS), the study area is defined extending from the boundary between the Upper Laguna Madre and Corpus Christi Bay to the north and the intersection of Laguna Madre and Baffin Bay to the south.

Packery Channel will provide a dredged channel across North Padre Island between the Upper Laguna Madre and the Gulf of Mexico. The channel is located east-southeast of the John F. Kennedy (JFK) Causeway, which crosses the Laguna Madre between the city of Corpus Christi and Padre Island (Figure 1). The proposed project will extend an existing 2.6-mile channel between the Gulf Intracoastal Waterway (GIWW) and State Highway 361 (SH 361) to the Gulf, an additional 0.9 mile. The existing channel is largely the result of the modern dredging of a historically shallow cut between what was the historic Packery Channel pass and Laguna Madre constructed under Department of Army Permit No. 17768. This channel was permitted for a 30- to 50-foot bottom width and a 5-foot depth. To the south and west of the currently proposed project is land that has been modified for recreational, commercial, and residential development as well as undeveloped land. North and west of the proposed channel, the land is relatively undeveloped and includes the Mollie Beattie Habitat Community (MBHC), a State-Federal cooperative preserve on State-owned land. The project area is easily accessible by vehicle or boat from Corpus Christi and is extensively used for recreation. The area of project construction east of SH 361 will occur in part of J.P. Luby Park, a public recreational facility.

The Galveston District of the USACE completed a 905(b) analysis of the potential project, dated 6 November 1998. The 905(b) analysis was authorized by Section 442 of the Water Resources Development Act (WRDA) of 1996 (P.L. 104-303, Sec. 442) and directed by the USACE to determine whether there would be a potential Federal interest in a project for environmental restoration, flood damage reduction, navigation, and/or related purposes in the vicinity of Packery Channel. The analysis recommended that the necessary feasibility-level studies be conducted to characterize the potential benefits in more detail and to identify the most cost-effective project features to realize them.

The USACE produced a Project Study Plan (PSP) in 1999 (USACE, 1999) that included a study of three alternative locations and three different channel widths, under three salinity regimes, to determine the environmental benefits of an opening between the Laguna Madre and the Gulf of Mexico. The study was also to provide information to help the study sponsor assess the likelihood of project authorization for construction upon conclusion of the Feasibility Study (FS). The analysis showed that a new water-exchange pass would significantly ameliorate high salinity episodes in the Upper Laguna

TABLE 1  
 FEDERALLY ENDANGERED AND THREATENED SPECIES OF POTENTIAL  
 OCCURRENCE IN THE PACKERY CHANNEL PROJECT AREA  
 IN NUECES COUNTY, TEXAS<sup>1</sup>

Common Name	Scientific Name	Status <sup>2</sup>
South Texas ambrosia	<i>Ambrosia cheiranthifolia</i>	E
Black lace cactus	<i>Echinocereus reichenbachii</i> var. <i>albertii</i>	E
Slender rush-pea	<i>Hoffmannseggia tenella</i>	E
Kemp's ridley sea turtle	<i>Lepidochelys kempii</i>	E
Green sea turtle	<i>Chelonia mydas</i>	T
Loggerhead sea turtle	<i>Caretta caretta</i>	T
Hawksbill sea turtle	<i>Eretmochelys imbricata</i>	E
Leatherback sea turtle	<i>Dermochelys coriacea</i>	E
Brown pelican	<i>Pelecanus occidentalis</i>	E
Bald eagle	<i>Haliaeetus leucocephalus</i>	T/PDL
Whooping crane	<i>Grus americana</i>	E
Northern aplomado falcon	<i>Falco femoralis septentrionalis</i>	E
Piping plover	<i>Charadrius melodus</i>	T
Mountain plover	<i>Charadrius montanus</i>	PT
Eskimo curlew	<i>Numenius borealis</i>	E
Ocelot	<i>Leopardus pardalis</i>	E
Jaguarundi	<i>Herpailurus yagouaroundi</i>	E
West Indian manatee	<i>Trichechus manatus</i>	E

<sup>1</sup> According to U.S. Fish & Wildlife Service (FWS, 2000a).

<sup>2</sup> E Endangered; in danger of extinction.


T Threatened; severely depleted or impacted by man.

PT Proposed for listing as threatened.

T/PDL Currently classified as threatened but proposed for delisting in lower 48 states.



-  Project Area
-  Roads
-  County Line
-  Mile Marker



206 Wild Basin Rd., Ste. 300  
 Austin, Texas 78746-3343  
 Phone: (512) 329-8342 Fax: (512) 327-2453

**Figure 1**  
**Location Map**

Prepared for: USACE	
Job No.: 440561	Scale: 1:250,000
Prepared by: G. Rackley	Date: June 2001
File: N:\440561\arcview\location map.apr (location map)	

Madre. However, these episodes are relatively rare, occurring on an average of about 1 year in 5; therefore, the potential environmental benefits to marine resources and area wildlife to be achieved by the project would be negligible.


Upon completion of the PSP, the USACE was directed by Congress under the WRDA 1999 CPL 106-53 (Sec. 556 entitled "North Padre Island Storm Damage Reduction and Environmental Restoration Project") to "carry out a project for ecosystem restoration and storm damage reduction at North Padre Island, Corpus Christi, Texas." Because of the magnitude, potential impacts, new compliance requirements, and the political controversy of this project, an EIS is being prepared. This BA has been prepared to assist the U.S. Fish and Wildlife Service (FWS) and National Marine Fisheries Service (NMFS) personnel in fulfilling their obligations under the ESA and will be incorporated into the DEIS.

## 1.2 DESCRIPTION OF THE PROPOSED ACTIONS

The length of the proposed channel from the Gulf end of the jetties to the Gulf Intracoastal Waterway (GIWW) is approximately 18,500 feet (3.5 miles). The Packery Channel alignment follows an existing channel southeast of the GIWW for approximately 2.6 miles to a basin southeast of State Highway 361 (SH 361). From this basin the proposed new channel will extend approximately 0.9 mile toward the Gulf (Figure 2). Packery Channel traffic will allow recreational and small commercial boats access between the GIWW and the Gulf. Traffic will not include large commercial ships, tows, deepwater draft barges, or any floating vessel with a draft greater than 4 feet.

According to the design engineer, URS/Dames & Moore (URS, 2002), the proposed channel opening involves dredging a new channel from the Gulf into the existing basin area (the Inner Basin) located southeast of the SH 361 bridge (Reach 1). Two impermeable rock jetties will extend from the shoreline approximately 1,400 feet paralleling the channel. The Inner Basin will be widened and deepened. The existing Packery Channel west of SH 361 (Reach 2) that extends to the GIWW will also be widened and deepened.

Approximately 810,000 cubic yards (cy) of new work material will be dredged. In addition, 56,200 cy will be excavated from PA 1 prior to placement of new work material. The dredged material will be placed in four placement areas (PAs) and a maintenance material placement area (MMPA). Approximately 128,800 cy will be placed on the south side of the channel between the existing seawall and the proposed shoreline protection bulkhead at PA 1; 76,000 cy on the north side of the channel to the north of the proposed shoreline protection bulkhead at PA 2; 60,400 cy on the south side of the channel between the existing seawall, the proposed shoreline protection bulkhead and SH 361 at PA 3; and 544,800 cy on the beach in front of the seawall on North Padre Island at PA 4S. The MMPA is proposed as an upland confined PA located south of the channel on city of Corpus Christi property. This site will accommodate anticipated maintenance dredging of 15,000 cy of material every 5 years for the 50-year project site. A sand bypass system will be utilized to move sand from the areas north and south of the jetties to designated beach areas. All maintenance material of high sand content will be used for beach nourishment in either PA 4S or PA 4N, located 500 feet south and north of the jetties, respectively.



Prepared for: USACE  
 Job No.: 440561  
 Scale: 1"=2700' for 8.5"x11" Sheet  
 Drawn by: G. Rockley  
 Date: March 2002  
 File: N:\440561\cod\utm83\_147\fig-2.dgn

**Figure 2**  
**Proposed Packery Channel**  
**and Placement Areas**

206 Wild Basin Rd., Ste. 300  
 Austin, Texas 78746-3343  
 Phone: (512) 329-6342 FAX: (512) 327-2453



Approximately 11,057,500 cy of maintenance material will be generated over the 50-year life of the project.

[This page intentionally left blank.]

## 2.0 IMPACT ASSESSMENT FOR LISTED SPECIES

To assess the potential impacts of the proposed project on endangered and threatened species, PBS&J personnel (1) conducted a literature review and searched for other scientific data to determine species distributions, habitat needs and other biological requirements; (2) interviewed recognized experts on the listed species, including local and regional authorities and Federal and State wildlife personnel; and (3) conducted an on-site inspection of the biological resources of the project area.

Significant literature sources consulted for this report include the FWS series on endangered species of the seacoast of the U.S. (National Fish and Wildlife Laboratories (NFWL), 1980), Federal status reports and recovery plans, and job reports of the Texas Parks and Wildlife Department (TPWD). A field survey of the project area was performed by PBS&J ecologists on 17 February 1999.

Of the 18 endangered species potentially present in the project area, only impacts to the piping plover have been identified as a result of this project. As discussed in detail below, impacts to piping plover Critical Habitat will result from this project. A total of 6.2 acres of Critical Habitat will be destroyed by construction of the jetties and channel. An additional 24.6 acres of Critical Habitat will be impacted annually by placement of new construction and maintenance material. Because of the abundance of algal flats and sand flats in the adjacent Critical Habitat areas, paired with the heavy recreational and vehicular use of the beach areas to be impacted, impacts to Critical Habitat from dredging and dredged material placement are considered to be minor. Therefore, impacts to the piping plover are not expected to jeopardize the species' existence.

## 2.1 SOUTH TEXAS AMBROSIA

### 2.1.1 Reasons for Status

South Texas ambrosia (*Ambrosia cheiranthifolia*), also known as South Texas ragweed, was Federally listed as endangered in August 1994 (50 CFR Part 17; 23 September 1994). Primary threats to the survival of this species include a low natural reproductive rate and destruction or disturbance of its habitat (FWS, 1987). Most of the deep clay soils occurring in south Texas that could support habitat for South Texas ambrosia have been converted into agricultural use. Known stands of this species occur in ROWs along highways and railways, where the species is subject to weed-control measures, including mowing and herbicide applications (Turner, 1983). In addition, introduced species such as buffelgrass (*Cenchrus ciliaris*) and King Ranch bluestem (*Bothriochloa ischaemum* var. *songarica*) compete with South Texas ambrosia and other native plants.

### 2.1.2 Habitat

An erect, silvery to grayish-green, herbaceous perennial 4 to 12 inches tall, South Texas ambrosia is an inhabitant of open, clay loam to sandy loam prairies and savannahs. It occurs in the Gulf coastal grassland in a vegetation type containing dominant shrubs typical of a local edaphic phase of the Tamaulipan brushland (e.g., species of acacia (*Acacia* spp.), Texas ebony (*Pithecellobium flexicaule*),

and cenizo (*Leucophyllum frutescens*). Grasses typically occurring with South Texas ambrosia include perennials such as bluestems, paspalums (*Paspalum* spp.), and lovegrasses (*Eragrostis* spp.). South Texas ambrosia occurs in flat, deep, largely undisturbed clay soils or occasionally on wind-blown clay dunes along streams. Clay soils of extreme south Texas derived from the Beaumont clay series could be considered suitable for establishment of this species. Most known remnant populations are found along roadways, railways, and on disturbed sites (Lonard, 1987). South Texas ambrosia is difficult to detect because it is generally overtopped by grasses (Turner, 1983).

### 2.1.3 Range

South Texas ambrosia is known only from the southern tip of Texas and from Tamaulipas, Mexico (Correll and Johnston, 1970; Turner, 1983). It was first collected by J.L. Berlandier in San Fernando, Tamaulipas, Mexico, in 1835 (Turner, 1983), but it was not until 1859 that Gray described this species as new to science. Historically, South Texas ambrosia was known only from Kleberg, Nueces, Jim Wells, and Cameron counties in the Gulf Prairie region of Texas and Tamaulipas in Mexico. The status of the Mexican populations is unknown.

### 2.1.4 Distribution in Texas

The species has been reported from Jim Wells and Cameron counties, though currently verified in six general locations in Nueces and Kleberg counties (TPWD, 1999a).

### 2.1.5 Presence in the Project Area

This species is not expected to occur in the project area due to the lack of suitable soils. No specimens of this species were encountered in the project area during PBS&J's field efforts.

### 2.1.6 Effects of the Project

No impacts to this endangered plant are anticipated due to this project.

## 2.2 BLACK LACE CACTUS

### 2.2.1 Reasons for Status

Black lace cactus (*Echinocereus reichenbachii* var. *albertii*) was Federally listed as endangered on 26 October 1979 (44 FR 61918) and is also listed as endangered by the State of Texas (Poole et al., 2000). The greatest threat to the black lace cactus is habitat destruction, especially clearing of brush tracts for cultivation or for establishment of improved pastures of exotic grass species. Other threats include trampling by cattle and collecting by cactus enthusiasts (Gardner and O'Brien, 1987). Agricultural practices such as herbicide use are an additional threat.

## 2.2.2 Habitat

Although other varieties of lace cactus typically occur among rocks in limestone country, the black lace cactus occurs on brush tracts on sandy loam soils (Gardner and O'Brien, 1987). The habitat consists of brushy, grassy areas where the Gulf Coastal Plain meets the inland mesquite shrubland, with huisache (*Acacia farnesiana*), honey mesquite (*Prosopis glandulosa*), blackbrush (*Acacia rigidula*), retama (*Parkinsonia aculeata*), granjeno (*Celtis pallida*), guayacan (*Guaiacum angustifolia*), buffalograss (*Buchloe dactyloides*), and Texas grama (*Bouteloua rigidisetata*) (Poole and Riskind, 1987).

## 2.2.3 Range

The black lace cactus is a subspecies of the lace cactus (*Echinocereus reichenbachii*), which is well known and widely collected, ranging from western Kansas to northern Mexico (Bakeberg, 1977; Britton and Rose, 1963). Black lace cactus has been found in the Texas Gulf coast counties of Jim Wells, Kleberg, and Refugio (Gardner and O'Brien, 1987).

## 2.2.4 Distribution in Texas

The black lace cactus is known from three populations in Jim Wells, Kleberg, and Refugio counties (TPWD, 1999b), with an introduced population in Duval County (Poole et al., 2000).

## 2.2.5 Presence in the Project Area

This species is unlikely to occur in the project area due to the lack of suitable soils and habitat.

## 2.2.6 Effects of the Project

No impacts on the black lace cactus are expected from this project.

## 2.3 SLENDER RUSH-PEA

### 2.3.1 Reasons for Status

The slender rush-pea (*Hoffmanseggia tenella*) was Federally listed as endangered on 1 November 1985 (50 FR 45614) and is also listed by the State of Texas as endangered. It is alternately known with the spelling (*Hoffmannseggia tenella*), which is used in Federal and State documents. The greatest threats to this species are conversion of coastal prairie habitat to other land uses, herbicide use, and competition from non-native grasses such as King Ranch bluestem, Kleberg bluestem (*Dichanthium annulatum*), and bermudagrass (*Cynodon dactylon*) (TPWD, 1997).

### 2.3.2 Habitat

It grows on calcareous, clayey soils in prairies and creek bands associated with short and midgrasses such as buffalograss, Texas wintergrass (*Stipa leucotricha*), and Texas grama. Woody plants such as honey mesquite, huisache, huisachillo (*Acacia tortuosa*), granjeno, brasil (*Condalia hookeri*), retama, lotebush (*Zizyphus obtusifolia*), tasajillo (*Opuntia leptocaulis*), and pricklypear (*Opuntia* spp.) are also common at the known sites.

### 2.3.3 Range

The slender rush-pea is only known from Texas along the south Texas Gulf coast counties of Kleberg and Nueces (TPWD, 1999c).

### 2.3.4 Distribution in Texas

The slender rush-pea is known from only three or four populations in Kleberg and Nueces counties (TPWD, 1999c).

### 2.3.5 Presence in the Project Area

This species is unlikely to occur in the project area due to the lack of suitable soils and habitat.

### 2.3.6 Effects of the Project

No impacts on the slender rush-pea are expected from this project

## 2.4 KEMP'S RIDLEY SEA TURTLE

### 2.4.1 Reasons for Status

Kemp's ridley (*Lepidochelys kempii*) was listed as endangered throughout its range on 2 December 1970 (35 FR 18320). Populations of this species have declined since 1947, when an estimated 42,000 females nested in one day, to a total nesting population of approximately 1,000 in the mid-1980s. The decline of this species was primarily due to human activities including collection of eggs, fishing for juveniles and adults, killing adults for meat and other products, and direct take for indigenous use. In addition to these sources of mortality, Kemp's ridleys have been subject to high levels of incidental take by shrimp trawlers (FWS and NMFS, 1992; NMFS, 2000). The National Research Council's (NRC's) Committee on Sea Turtle Conservation estimated in 1990 that 86% of the human-caused deaths of juvenile and adult loggerheads and Kemp's ridleys resulted from shrimp trawling (Campbell, 1995). It is estimated that before the implementation of turtle excluder devices (TEDs) the commercial shrimp fleet killed between 500 and 5,000 Kemp's ridleys each year (NMFS, 2000). Kemp's ridleys have also been taken by pound nets, gill nets, hook and line, crab traps, and longlines.

Another problem shared by adult and juvenile sea turtles is the ingestion of manmade debris and garbage. Postmortem examinations of sea turtles found stranded on the south Texas coast from 1986 through 1988 revealed 54% (60 of the 111 examined) of the sea turtles had eaten some type of marine debris. Plastic materials were most frequently ingested and included pieces of plastic bags, polystyrene products, plastic pellets, balloons, rope, and fishing line. Non-plastic debris such as glass, tar, and aluminum foil were also ingested by the sea turtles examined. Much of this debris comes from offshore oil rigs, cargo ships, commercial and recreational fishing boats, research vessels, naval ships, and other vessels operating in the Gulf of Mexico. Laws enacted during the late-1980s to regulate this dumping are difficult to enforce over vast expanses of water. In addition to trash, pollution from heavy spills of oil or waste products pose additional threats (Campbell, 1995).

Further threats to this species include collisions with boats, explosives used to remove oil rigs, and entrapment in coastal power plant intake pipes (Campbell, 1995). Dredging operations affect Kemp's ridley turtles through incidental take and by degrading the habitat. Incidental take of ridleys has been documented with hopper dredges. In addition to direct take, channelization of the inshore and nearshore areas can degrade foraging and migratory habitat through spoil dumping, degraded water quality/clarity and altered current flow (FWS and NMFS, 1992).

Sea turtles are especially subject to human impacts during the time the females come ashore for nesting. Modifications to nesting areas can have a devastating effect on sea turtle populations. In many cases, prime sea turtle nesting sites are also prime real estate. If a nesting site has been disturbed or destroyed, female turtles may nest in inferior locations where the hatchlings are less likely to survive, or they may not lay any eggs at all. Artificial lighting from developed beachfront areas often disorients nesting females and hatchling sea turtles, causing them to head inland by mistake, often with fatal results. Adult females also may avoid brightly lit areas that would otherwise provide suitable nesting sites (FWS, 1998).

Today, under strict protection, the population appears to be in the early stages of recovery. Approximately 6,000 Kemp's ridley nests were recorded on Mexican beaches during the 2000 nesting season (Shaver, 2000). The increase likely can be attributed to two primary factors: full protection of nesting females and their nests in Mexico and the requirement to use TEDs in shrimp trawlers both in the U.S. and in Mexico (NMFS, 2000).

#### 2.4.2 Habitat

Kemp's ridleys inhabit shallow coastal and estuarine waters, usually over sand or mud bottoms. Adults are primarily shallow-water benthic feeders that specialize on crabs, especially portunid crabs, while juveniles feed on sargassum (*Sargassum* sp.) and associated infauna, and other epipelagic species of the Gulf of Mexico (FWS and NMFS, 1992). In some regions the blue crab (*Callinectes sapidus*) is the most common food item of adults and juveniles. Other food items include shrimp, snails, bivalves, sea urchins, jellyfish, sea stars, fish, and occasional marine plants (Pritchard and Marquez, 1973; Shaver, 1991; Campbell, 1995).

#### 2.4.3 Range

Adults are primarily restricted to the Gulf of Mexico, although juveniles may range throughout the Atlantic Ocean since they have been observed as far north as Nova Scotia (Musick, 1979) and in coastal waters of Europe (Brongersma, 1972). Important foraging areas include Campeche Bay, Mexico, and Louisiana coastal waters.

Almost the entire population of Kemp's ridleys nests on an 11-mile stretch of coastline near Rancho Nuevo, Tamaulipas, Mexico, some 190 miles south of the Rio Grande. A secondary nesting area occurs at Tuxpan, Veracruz, and sporadic nesting has been reported from Mustang Island, Texas, southward to Isla Aquada, Campeche. There have been several isolated nesting attempts scattered from North Carolina to Colombia.

Because of the dangerous population decline at the time, a head-starting program was carried out from 1978 to 1988. Eggs were collected from Rancho Nuevo and placed into polystyrene foam boxes containing Padre Island sand so that the eggs never touched the Ranch Nuevo sand. The eggs were flown to the U.S. and placed in a hatchery on Padre Island and incubated. The resulting hatchlings were allowed to crawl over the Padre Island beaches into the surf for imprinting purposes before being recovered from the surf and taken to Galveston for rearing. They were fed a diet of high-protein commercial floating pellets for 7 to 15 months before being released into Texas (mainly) or Florida waters (Caillouet et al., 1995). This program has shown some results. The first nesting from one of these head-started individuals occurred at Padre Island in 1996, and more nestings have occurred since (Shaver, 2000).

#### 2.4.4 Distribution in Texas

Kemp's ridley occurs in Texas in small numbers and in many cases may well be in transit between crustacean-rich feeding areas in the northern Gulf of Mexico and breeding grounds in Mexico. It has nested sporadically in Texas in the last 50 years. Nests were found near Yarbrough Pass in 1948 and 1950, and in 1960 a single nest was located at Port Aransas. The number of nestings, however, has increased in recent years. In 1999, 16 confirmed Kemp's ridley nests were recorded in Texas and 12 nests were confirmed for 2000 (Shaver, 2000). Several of the ridley nests were from head-started individuals. Such nestings, together with the proximity of the Rancho Nuevo rookery, probably accounts for the occurrence of hatchlings and subadults in Texas. According to Hildebrand (1982, 1986, 1987), sporadic ridley nesting in Texas has always been the case. This is in direct contradiction, however, to Lund (1974), who believed that Padre Island historically supported large numbers of nesting Kemp's ridleys, but that the population became extirpated because of excessive egg collection.

#### 2.4.5 Presence in the Project Area

Kemp's ridley has been recorded from Nueces County (Dixon, 2000) and from Corpus Christi Bay (Shaver, 2000). Thus, it is of potential occurrence in the project area.

#### 2.4.6 Effects of the Project

If it occurs in the project area, there is a slight chance that Kemp's ridley could potentially be negatively impacted by dredging activities during construction or by maintenance activities after construction, if hopper dredges are used. Hopper dredges move much more rapidly than cutterhead dredges and "can entrain and kill sea turtles, presumably as the drag arm of the moving dredge overtakes the slower moving turtle" (NMFS, 1998). However, cutterhead dredges move very slowly and can be avoided by all species of sea turtles. Studies have indicated that cutterhead dredges, since they act on only small areas at a time, do not impact sea turtles (NMFS, 1998). Since all dredging of the proposed Packery Channel will be performed by cutterhead dredges, or hopper dredges with turtle-deflecting dragheads, screens, and turtle observers, no impacts to Kemp's ridley sea turtles are anticipated from dredging.

This species could be attracted to feeding opportunities at the proposed jetties, where it would be exposed to minor risks from boat traffic, contaminants (in the unlikely event of a spill), fishing activities, tangled fishing lines, and accumulated plastic debris. Lighting and traffic from developments associated with the project could impact nesting activities, if they should occur in the vicinity. Potential nesting habitat could be removed when the washover area is dredged. Although occasional individuals may be negatively impacted by this project, the continued existence of the species is not likely to be jeopardized nor is take, as defined under Section 9 of the ESA, anticipated.

### 2.5 GREEN SEA TURTLE

#### 2.5.1 Reasons for Status

The green sea turtle (*Chelonia mydas*) was listed on 28 July 1978 as threatened except for Florida and the Pacific coast of Mexico (including the Gulf of California) where it was listed as endangered (43 FR 32808). The greatest cause of decline in green sea turtle populations is commercial harvest for eggs and food. Other turtle parts are used for leather and jewelry, and small turtles are sometimes stuffed for curios. Incidental catch during commercial shrimp trawling is a continued source of mortality that adversely affects recovery. It is estimated that before the implementation of TED requirements, the offshore commercial shrimp fleet captured about 925 green sea turtles a year, of which approximately 225 would die. Most turtles killed are juveniles and subadults. Various other fishing operations also negatively impact this species (NMFS, 2000). Epidemic outbreaks of fibropapilloma or "tumor" infections recently have occurred on green sea turtles, especially in Hawaii and Florida, posing a severe threat. The cause of these outbreaks is largely unknown, but it could be caused by a viral infection (Barrett, 1996). Some scientists suspect this disease to be linked to environmental alteration of sea turtle habitat by pollution and contaminants (FWS, 1998). This species is also subject to various negative impacts shared by sea turtles in general.

### 2.5.2 Habitat

The green sea turtle primarily utilizes shallow habitats such as lagoons, bays, inlets, shoals, estuaries, and other areas with an abundance of marine algae and seagrasses. Individuals observed in the open ocean are believed to be migrants en route to feeding grounds or nesting beaches (Meylan, 1982). Hatchlings often float in masses of sea plants (e.g., sargassum) in convergence zones. Coral reefs and rocky outcrops near feeding pastures often are used as resting areas. The adults are primarily herbivorous, while the juveniles consume more invertebrates. Foods consumed include seagrasses, macroalgae and other marine plants, molluscs, sponges crustaceans, and jellyfish (Mortimer, 1982; Green, unpubl. data).

Terrestrial habitat is typically limited to nesting activities, although in some areas, such as Hawaii and the Galápagos Islands, they will bask on beaches (Balazs, 1980; Green, unpubl. data). They prefer high energy beaches with deep sand, which may be coarse to fine, with little organic content. At least in some regions, they generally nest consistently at the same beach, which is apparently their natal beach (Meylan et al., 1990; Allard et al., 1994), although an individual might switch to a different nesting beach within a single nesting season (Green, unpubl. data).

### 2.5.3 Range

The green sea turtle is a circumglobal species in tropical and sub-tropical waters. In U.S. Atlantic waters, it is found around the U.S. Virgin Islands, Puerto Rico, and continental U.S. from Massachusetts to Texas. Major nesting activity occurs on Ascension Island, Aves Island (Venezuela), Costa Rica, and in Surinam. Relatively small numbers nest in Florida, with even smaller numbers in Georgia, North Carolina, and Texas (NMFS and FWS, 1991a; Hirth, 1997).

### 2.5.4 Distribution in Texas

The green sea turtle in Texas inhabits shallow bays and estuaries where its principal foods, the various marine grasses, grow (Bartlett and Bartlett, 1999). Its population in Texas has suffered a decline similar to that of its world population. In the mid- to late-nineteenth century, Texas waters supported a green sea turtle fishery. Most of the turtles were caught in Matagorda Bay, Aransas Bay, and the Lower Laguna Madre, although a few also came from Galveston Bay. Many live turtles were shipped to places such as New Orleans or New York and from there to other areas. Others were processed into canned products such as meat or soup prior to shipment. By 1900, however, the fishery had virtually ceased to exist. Turtles continued to be hunted sporadically for a while, the last Texas turtler hanging up his nets in 1935. Incidental catches by fisherman and shrimpers were sometimes marked prior to 1963, when it became illegal to do so (Hildebrand, 1982).

Green sea turtles can still be found in these same bays today but in much-reduced numbers (Hildebrand, 1982). While green sea turtles prefer to inhabit bays with seagrass meadows, they may also be found in bays that are devoid of seagrasses. The green sea turtles in these Texas bays are

mainly small juveniles. Adults, juveniles, and even hatchlings are occasionally caught on trotlines or by offshore shrimpers or are washed ashore in a moribund condition.

Green sea turtle nests are rare in Texas. The most recent, a single nest, occurred in 2000; no green sea turtle nests were recorded in 1999. In comparison, 16 Kemp's ridley and 2 loggerhead nests were recorded in 1999 and 12 Kemp's ridley and 5 loggerhead nests were recorded in 2000 (Shaver, 2000). Green sea turtles, however, nest in Florida and in Mexico. Since long migrations of green sea turtles from their nesting beaches to distant feedings grounds are well documented (Meylan, 1982; Green, 1984), the adult green sea turtles occurring in Texas may either be at their feeding grounds or in the process of migrating to or from their nesting beaches. The juveniles frequenting the seagrass meadows of the bay areas may remain there until such time as they move to other feeding grounds or, perhaps, once having attained sexual maturity, return to their natal beaches outside of Texas to nest.

#### 2.5.5 Presence in the Project Area

The green sea turtle has been recorded from Nueces County (Dixon, 2000) and has been recorded from Corpus Christi Bay (Shaver, 2000). It is of potential occurrence in the project area.

#### 2.5.6 Effects of the Project

No negative impacts to the green sea turtle from dredging activities during construction or maintenance of Packery Channel are expected, for the reasons stated in Section 2.4.6. This species could also be attracted to feeding opportunities at the proposed jetties and channel, where it would be exposed to additional risks from boat traffic, contaminants (in the unlikely event of a spill), fishing activities, tangled fishing lines, and accumulated plastic debris. The channel might facilitate passage by the turtles between the open Gulf of Mexico and feeding areas in the seagrass beds of the Laguna Madre. It is not known what the long-range impacts the proposed project might have on seagrass beds near the project channel related to potential scouring, increased boat activity, and dredging activities, but no direct negative impacts to the seagrass beds of the Laguna Madre are anticipated. Lighting and traffic from developments associated with the project could impact nesting activities, if they should occur in the vicinity, although such nestings are extremely rare (see above). Construction of jetties and bulkheads could provide some additional foraging habitat by providing a substrate on which algae could grow. Although occasional individuals could potentially be negatively impacted by this project, the continued existence of the species will not be jeopardized nor is take, as defined under Section 9 of the ESA, anticipated.

### 2.6 LOGGERHEAD SEA TURTLE

#### 2.6.1 Reasons for Status

The loggerhead turtle (*Caretta caretta*) was listed as threatened throughout its range on 28 July 1978 (43 FR 32808). The decline of the loggerhead, like that of most sea turtles, can be attributed to overexploitation by man, inadvertent mortality associated with fishing and trawling activities,

and natural predation. The most significant threats to its population are coastal development, commercial fisheries, and pollution (NMFS, 2000).

#### 2.6.2 Habitat

The loggerhead is found in the open seas as far as 500 miles from shore, but mainly over the continental shelf, and in bays, estuaries, lagoons, creeks, and mouths of rivers. It favors warm temperate and sub-tropical regions not far from shorelines. The adults occupy various habitats, from turbid bays to clear waters of reefs. Subadults occur mainly in nearshore and estuarine waters. Hatchlings move directly to sea after hatching, and often float in masses of sargassum. They may remain associated with sargassum for perhaps 3 to 5 years (NMFS and FWS, 1991b).

Commensurate with their use of varied habitats, loggerheads consume a wide variety of both benthic and pelagic food items, which they crush before swallowing. Conches, shellfish, horseshoe crabs, prawns and other crustacea, squid, sponges, jellyfish, basket stars, fish (carrion or slow-moving species), and even hatchling loggerheads have all been recorded as loggerhead prey (Rebel, 1974; Hughes, 1974; Mortimer, 1982). Adults forage primarily on the bottom, but also take jellyfish from the surface. The young feed on prey concentrated at the surface, such as gastropods, fragments of crustaceans, and sargassum.

Nesting occurs usually on open sandy beaches above high-tide mark and seaward of well developed dunes. They nest primarily on high-energy beaches on barrier islands adjacent to continental land masses in warm-temperate and sub-tropical regions. Steeply sloped beaches with gradually sloped offshore approaches are favored. In Florida, nesting on urban beaches was strongly correlated with the presence of tall objects (trees or buildings), which apparently shield the beach from city lights (Salmon et al., 1995).

#### 2.6.3 Range

The loggerhead is widely distributed in tropical and subtropical seas, being found in the Atlantic Ocean from Nova Scotia to Argentina, Gulf of Mexico, Indian and Pacific oceans (although it is rare in the eastern and central Pacific) and the Mediterranean Sea (Rebel, 1974; Ross, 1982; Iverson, 1986). In the continental U.S., loggerheads nest along the Atlantic coast from Florida to as far north as New Jersey (Musick, 1979) and sporadically along the Gulf coast. In recent years a few have nested on barrier islands along the Texas coast.

#### 2.6.4 Distribution in Texas

The loggerhead is considered to be the most abundant turtle in Texas marine waters, preferring shallow inner continental shelf waters and occurring only very infrequently in the bays. It is also the species most commonly sighted around offshore oil rig platforms and reefs and jetties. Loggerheads are probably present year-round but are most noticeable in the spring when one of their food items, the Portuguese Man-of-War, is abundant. Loggerheads constitute a major portion of the dead or moribund turtles washed ashore (stranded) on the Texas coast each year. A large proportion of these

deaths is due to the activities of shrimp trawlers where turtles are accidentally caught in the nets and drown and their bodies dumped overboard. Prior to 1977, no positive documentation of loggerhead nests in Texas existed (Hildebrand, 1982). Since that time, several nests have been recorded along the Texas coast. In 1999, two loggerhead nests were confirmed in Texas, while in 2000, five loggerhead nests were confirmed (Shaver, 2000). Like the worldwide population, the population of loggerheads in Texas has declined. Prior to World War I, the species was taken in Texas for local consumption and a few were marketed (Hildebrand, 1982). Today, even without protection, insufficient loggerheads exist to support a fishery.

#### 2.6.5 Presence in the Project Area

The loggerhead has been recorded in Nueces County (Dixon, 2000) and from Corpus Christi Bay (Shaver, 2000). It is of potential occurrence in the project area.

#### 2.6.6 Effects of the Project

No negative impacts to the loggerhead, if it occurs in the project area, are expected from dredging activities during construction or maintenance of Packery Channel, for the reasons stated in Section 2.4.6. This species could also be attracted to feeding opportunities at the proposed jetties and channel, where it would be exposed to additional risks from boat traffic, contaminants (in the unlikely event of a spill), fishing activities, tangled fishing lines, and accumulated plastic debris. Lighting and traffic from developments associated with the project could impact nesting activities, if they should occur. Potential nesting habitat could be removed when dredging the washover. Construction of jetties and bulkheads could provide additional foraging habitat for the loggerhead turtle. Although there is the potential for negative impacts to occasional individuals due to this project, the continued existence of the species will not be jeopardized nor is take, as defined under Section 9 of the ESA, anticipated.

### 2.7 HAWKSBILL SEA TURTLE

#### 2.7.1 Reasons for Status

The hawksbill turtle (*Eretmochelys imbricata*) was Federally listed as endangered on 2 June 1970 (35 FR 8495) with Critical Habitat designated in Puerto Rico on 24 May 1978 (43 FR 22224). The greatest threat to this species is harvest to supply the market for tortoiseshell and stuffed turtle curios (Meylan and Donnelly, 1999). Hawksbill shell (bekko) commands high prices (recently \$225/kilogram (kg)). Japanese imports of raw bekko between 1970 and 1989 totaled 713,850 kg, representing more than 670,000 turtles. The hawksbill is also used in the manufacture of leather, oil, perfume, and cosmetics (NMFS, 2000).

#### 2.7.2 Habitat

Hawksbills generally inhabit coastal reefs, bays, rocky areas, passes, estuaries, and lagoons, where they are typically found at depths of less than 70 ft. Like some other sea turtle species, hatchlings are sometimes found floating in masses of marine plants (e.g., sargassum rafts) in the open

ocean (NFWL, 1980). Hawksbills reenter coastal waters when they reach a carapace length of approximately 20 to 25 centimeters. Coral reefs are widely recognized as the resident foraging habitat of juveniles, subadults, and adults. This habitat association is undoubtedly related to their diet of sponges, which need solid substrate for attachment. Hawksbills are also found around rocky outcrops and high-energy shoals, which are also optimum sites for sponge growth. In Texas, juvenile hawksbills are associated with stone jetties (NMFS, 2000).

While this species is omnivorous, it prefers invertebrates, especially encrusting organisms, such as sponges, tunicates, bryozoans, mollusks, corals, barnacles, and sea urchins. Pelagic species consumed include jellyfish and fish, and plant material such as algae, sea grasses and mangroves, has also been reported as food items for this turtle (Carr, 1952; Rebel, 1974; Pritchard, 1977; Musick, 1979; Mortimer, 1982). The young are reported to be somewhat more herbivorous than the adults (Ernst and Barbour, 1972).

Terrestrial habitat is typically limited to nesting activities. They nest on undisturbed, deep-sand beaches, from high-energy ocean beaches to tiny pocket beaches several meters wide bounded by crevices of cliff walls. Typically, the sand beaches are low energy, with woody vegetation, such as sea grape (*Coccoloba uvifera*), near the waterline (NRC, 1990). The hawksbill is typically a solitary nester, which makes it harder to monitor nesting activity and success (NMFS, 2000).

#### 2.7.3 Range

The hawksbill is circumtropical, occurring in tropical and subtropical seas of the Atlantic, Pacific, and Indian oceans (Witzell, 1983). This species is probably the most tropical of all marine turtles, although it does occur in many temperate regions. The hawksbill turtle is widely distributed in the Caribbean Sea and western Atlantic Ocean, with representatives of at least some life history stages regularly occurring in southern Florida and the northern Gulf of Mexico (especially Texas), south to Brazil (NMFS, 2000). In the continental U.S., the hawksbill nests only in Florida where it is sporadic at best (NFWL, 1980). However, a major nesting beach exists on Mona Island, Puerto Rico. Elsewhere in the western Atlantic, hawksbills nest in small numbers along the Gulf coast of Mexico, the West Indies, and along the Caribbean coasts of Central and South America (Musick, 1979).

#### 2.7.4 Distribution in Texas

Texas is the only State outside of Florida where hawksbills are sighted with any regularity. Most of these sightings involve posthatchlings and juveniles, and are primarily associated with stone jetties. These small turtles are believed to originate from nesting beaches in Mexico (NMFS, 2000).

#### 2.7.5 Presence in the Project Area

The hawksbill has been recorded from Nueces County (Dixon, 2000) and from Corpus Christi Bay (Shaver, 2000). It is of potential, though unlikely, occurrence in the area to be dredged.

## 2.7.6 Effects of the Project

Because most of the sightings of the hawksbill sea turtle in the northern Gulf of Mexico occur at stone jetties, this species could occur near the proposed jetties and bulkheads. However, no negative impacts to the hawksbill sea turtle from dredging activities during construction or maintenance of Packery Channel are expected, for the reasons stated in Section 2.4.6. This species could also be attracted to feeding opportunities at the proposed jetties and channel, where it would be exposed to additional risks from boat traffic, contaminants (in the unlikely event of a spill), fishing activities, tangled fishing lines, and accumulated plastic debris. Construction of jetties and bulkheads could provide additional foraging habitat for the hawksbill sea turtle. Although occasional individuals could potentially be negatively impacted by this project, the continued existence of the species will not be jeopardized nor is take, as defined under Section 9 of the ESA, anticipated.

## 2.8 LEATHERBACK SEA TURTLE

### 2.8.1 Reasons for Status

The leatherback turtle (*Dermochelys coriacea*) was listed as endangered throughout its range on 2 June 1970 (35 FR 8495), with Critical Habitat designated in the U.S. Virgin Islands on 26 September 1978 and 23 March 1979 (43 FR 43688/43689 and 44 FR 17710/17712, respectively). Its decline is attributable to overexploitation by man and incidental mortality associated with commercial shrimping and fishing activities. Use of turtle meat for fish bait and the consumption of litter by turtles have also been mentioned as causes for mortality, the latter phenomenon apparently occurring when plastic is mistaken for jellyfish (Rebel, 1974). While nesting populations of leatherback sea turtles are especially difficult to discern because the females frequently change nesting beaches, current estimates are that 20,000 to 30,000 female leatherbacks exist worldwide. The major threat is egg collecting, although they are jeopardized to some extent by destruction or degradation of nesting habitat (NatureServe, 2000). Egg collecting is not currently a problem in Florida, but remains a problem in Puerto Rico and the U.S. Virgin Islands (NMFS and FWS, 1992). This species is probably more susceptible than other turtles to drowning in shrimp trawlers equipped with TEDs because adult leatherbacks are too large to pass through the TED exit opening. Because leatherbacks nest in the tropics during hurricane season, a potential exists for storm-generated waves and wind to erode nesting beaches, resulting in nest loss (NMFS and FWS, 1992).

### 2.8.2 Habitat

The leatherback turtle is mainly pelagic, inhabiting the open ocean, and seldom approaches land except for nesting (Eckert, 1992). It is most often found in coastal waters only when nesting or when following concentrations of jellyfish (TPWD, 2000), when it can be found in inshore waters, bays, and estuaries. It dives almost continuously, often to great depths.

Despite their large size, the diet of leatherbacks consists largely of jellyfish and sea squirts. They also consume sea urchins, squid, crustaceans, fish, blue-green algae, and floating

seaweed (NFWL, 1980). The leatherback typically nests on beaches with a deepwater approach (Pritchard, 1971).

### 2.8.3 Range

The leatherback is probably the most wide-ranging of all sea turtle species. It is found in the Atlantic, Pacific and Indian oceans; as far north as British Columbia, Newfoundland, Great Britain and Norway; as far south as Australia, Cape of Good Hope, and Argentina; and in other water bodies such as the Mediterranean Sea (NFWL, 1980). Leatherbacks nest primarily in tropical regions; major nesting beaches include Malaysia, Mexico, French Guiana, Surinam, Costa Rica, and Trinidad (Ross, 1982). Leatherbacks nest only sporadically in some of the Atlantic and Gulf states of the continental U.S., with one nesting reported as far north as North Carolina (Schwartz, 1976). In the Atlantic and Caribbean, the largest nesting assemblages are found in the U.S. Virgin Islands, Puerto Rico, and Florida (NMFS, 2000).

The leatherback migrates further and ventures into colder water than any other marine reptile. Adults appear to engage in routine migrations between boreal, temperate, and tropical waters, presumably to optimize both foraging and nesting opportunities. The longest-known movement is that of an adult female that traveled 5,900 km to Ghana, West Africa, after nesting in Surinam (NMFS and FWS, 1992). During the summer, leatherbacks tend to be found along the east coast of the U.S. from the Gulf of Maine south to the middle of Florida.

### 2.8.4 Distribution in Texas

Apart from occasional feeding aggregations such as one of 100 animals reported by Leary (1957) off Port Aransas in December 1956, or possible concentrations in the Brownsville Eddy in winter (Hildebrand, 1983), leatherbacks are rare along the Texas coast, tending to keep to deeper offshore waters where their primary food source, jellyfish, occurs. In the Gulf of Mexico the leatherback is often associated with two species of jellyfish: the cabbagehead (*Stomolophus* sp.) and the moon jellyfish (*Aurelia* sp.) (NMFS and FWS, 1992). According to FWS (1981), leatherbacks never have been common in Texas waters. No nests of this species have been recorded for at least 60 years. The last two, one from the late 1920s and one from the mid-1930s, were both from Padre Island (Hildebrand, 1982, 1986).

### 2.8.5 Presence in the Project Area

While the leatherback has been recorded from Nueces County (Dixon, 2000), it is unlikely to occur in the project area.

### 2.8.6 Effects of the Project

Of the five species of sea turtles occurring in Texas waters, the leatherback is the species least likely to be affected by the proposed project because of its rare occurrence and pelagic nature. No adverse effects to this species are anticipated as a result of the project.

## 2.9 BROWN PELICAN

### 2.9.1 Reasons for Status

The brown pelican (*Pelecanus occidentalis*) was listed as endangered throughout its foreign range on 2 June 1970 (35 FR 8495) and throughout its U.S. range on 13 October 1970 (35 FR 16047). Population declines were attributed largely to chlorinated hydrocarbon residues from the use of pesticides, such as DDT compounds (DDE, DDD and DDT), polychlorinated biphenyls (PCBs), dieldrin, and endrin which caused eggshell thinning; thus eggs became desiccated and were more easily broken during incubation (NFWL, 1980). Other factors included human disturbance and loss of habitat due to commercial and residential development (FWS, 1995). Pelicans are large, heavy birds and easily flushed from the nest. Flushing exposes the eggs and young to predation, temperature stress and permanent abandonment by the parents.

A ban on the use of DDT in the U.S. in 1972, together with efforts to conserve and improve remaining populations, has led to increased numbers of brown pelicans. Populations in some areas have increased to historical breeding levels or above, with stable population numbers and productivity. The brown pelican has been delisted along the U.S. Atlantic coast and, in Florida and Alabama, along the Gulf coast. It remains endangered throughout the rest of its range, which includes Mississippi, Louisiana, Texas, California, Mexico, Central and South America, and the West Indies. In May 1998, the FWS announced its intention to either delist or downlist to threatened status numerous species, including the brown pelican (63 FR 25502-25512; 8 May 1998).

### 2.9.2 Habitat

Brown pelicans inhabit shallow coastal waters with water depths up to 80 ft (Palmer, 1962; NFWL, 1980; Fritts et al., 1983). They are rarely found inland and do not venture more than 20 miles out to sea except to take advantage of particularly good feeding situations (FWS, 1980). Distances of 61 miles from shore have been recorded (Fritts et al., 1983). Brown pelicans, which are colonial nesters, usually nest on undisturbed offshore islands in small bushes and trees, including mangroves, and in humid forests (NFWL, 1980; Guzman and Schreiber, 1987). Occasionally they nest on the ground. Preferred sites are those free from human disturbance, flooding and terrestrial predators such as raccoons. Brown pelicans utilize beaches, sandbars, sandspits, mud flats and even manmade structures such as piers, wharves, pilings, oil/gas platforms, and docks for loafing (NFWL, 1980).

### 2.9.3 Range

The brown pelican occurs along the Pacific coast of the Americas from southern British Columbia south to Cape Horn, and throughout the Atlantic, Gulf and Caribbean coastal areas from New Jersey south to eastern Venezuela. In North America, it occasionally ventures inland north to North Dakota, Ontario and Nova Scotia. Its breeding range is more restricted: along the Pacific coast from central California south to Chile, including the Galápagos Islands; and from North Carolina, south to

eastern Venezuela, the West Indies, Greater Antilles, and Virgin Islands (American Ornithologists' Union (AOU), 1998).

In North America, two subspecies are recognized: the eastern brown pelican (*P.o. carolinensis*) ranging from North Carolina south through Florida and west to Texas, and the California brown pelican (*P.o. californicus*) in California (NFWL, 1980). For the eastern subspecies, the present range is the same as the historical one, but in reduced numbers. It became extirpated in Louisiana in 1966, but has since (beginning in 1968) been reintroduced from Florida. It has never been known to nest in Mississippi or Georgia (FWS, 1980; 50 FR 4938, 9 February 1985). Brown pelican colonies are known to occur on the east coast of Mexico off the eastern tip of the Yucatan Peninsula (Mabie, 1986, 1988).

While some migration occurs after nesting in both subspecies, many individuals overwinter close to their breeding grounds (FWS, 1980). Atlantic coast populations move southward in the fall, with most birds wintering in the U.S., particularly in Florida. Some birds, however, disperse to the Cuban coast (Clapp et al., 1982). Gulf coast birds tend to remain on the Gulf coast, although Texas and Louisiana birds have been recovered in Mexico and Cuba (Palmer, 1962; Clapp et al., 1982).

#### 2.9.4 Distribution in Texas

Historically, the brown pelican was a common bird of the Texas Gulf coast with an estimated breeding population of 5,000 pairs residing in 17 colonies in 1918 (Mabie, 1990). By the 1960s, however, it was almost extirpated. In 1963, only 14 breeding pairs were recorded along the Texas coast; in 1964 no known nesting occurred (Mabie, 1986). The decline started during the 1920s and 1930s due to human disturbance (Oberholser, 1974), but has continued due to pesticide contamination (King et al., 1977; Mabie, 1986). Since the 1960s, the brown pelican has made a gradual comeback in Texas with an estimated 2,400 breeding pairs in 1995 (Campbell, 1995). Most of the breeding birds are found on Pelican Island in Corpus Christi Bay, Nueces County, and Sundown Island near Port O'Connor in Matagorda County. Smaller groups or colonies occasionally nest on Bird Island in Matagorda Bay, a series of older dredged material islands in West Matagorda Bay, Dressing Point Island in East Matagorda Bay, and islands in Aransas Bay (Campbell, 1995). No nesting sites are known from the lower Texas Coast. Although brown pelican colonies are not monitored every year, 1,100 pairs nested on Pelican Island in 2000, while on Sundown Island, 698 pairs nested in 2000 and 1,200 pairs nested in 1999 (FWS, 2000b).

#### 2.9.5 Presence in the Project Area

In Texas, the brown pelican occurs from Chambers County to Cameron County (Campbell, 1995) and primarily along the lower and middle coasts. Occasional sightings are reported on the upper coast and inland to central, north-central, and eastern Texas (Texas Ornithological Society (TOS), 1995), usually on large freshwater lakes. Such occurrences are relatively uncommon. Pelican Island is located in Corpus Christi Bay approximately 14 miles north of the proposed project. Brown pelicans likely occur in the project area and immediate vicinity.

## 2.9.6 Effects of the Project

This species is expected to forage in the project area or general vicinity on occasion, and it could potentially be temporarily affected from noise and activity from the proposed project. Because the nearest active nesting colony is at Pelican Island approximately 14 miles north of the proposed project, nesting pelicans will not be impacted by the project. No adverse effects are anticipated as a result of this project which would jeopardize the continued existence of this species or constitute a take, as defined under Section 9 of the ESA.

## 2.10 BALD EAGLE

### 2.10.1 Reasons for Status

The bald eagle (*Haliaeetus leucocephalus*) was first granted legal protection with the Eagle Protection Act, passed on 8 June 1940 and amended 23 October 1972. The species was listed as endangered below the 40th parallel on 11 March 1967 (32 FR 4001) and later received protection under the Endangered Species Act of 1973. The legal status of the species was changed on 14 February 1978 (43 FR 6233) to endangered in the conterminous U.S. except for Washington, Oregon, Minnesota, Wisconsin, and Michigan, where it was designated as threatened (FWS, 1984). The bald eagle recovered sufficiently to be downlisted to threatened throughout its range and FWS has proposed to completely delist the species in the near future (64 FR 36453-36464; 6 July 1999).

Several factors have contributed to the decline of the bald eagle since the settling of North America. The primary factor in direct loss is shooting (Snow, 1981). Mortality through shooting, however, is on the decline. Between 1975 and 1981, 18% of the total reported mortalities were due to shooting, compared to 62% between 1961 and 1965 (FWS, 1984).

Historically, increase in human population has resulted in extensive alterations in land use. Because the eagles nest near water, increased recreation and other human use of water resources have had negative effects on the bald eagle. The greater use of boats, off-road vehicles, and snowmobiles, and increased development of waterfront property have severely altered eagle habitat (Snow, 1981). New wintering and non-nesting habitat, however, is now being created by the construction of reservoirs, which may also be used more in the future by nesting eagles, potentially resulting in a major redistribution of nesting (FWS, 1984).

Environmental contaminants are responsible for the greatest decline in eagle populations. Organochloride pesticides inhibit calcium metabolism, resulting in thin eggshells and, thus, reproductive failure. Since the use of DDT and other organochloride pesticides was banned in the U.S., the eagles have slowly recovered. Most populations of bald eagles appear to be producing young at a normal rate (FWS, 1984).

### 2.10.2 Habitat

The bald eagle inhabits coastal areas, rivers and large bodies of water. Water is the common feature of its nesting habitat (Green, 1985). Because fish and waterfowl comprise the bulk of the bald eagle's diet, nests of the species are seldom far from a river, lake, bay, or other water body. Nests are generally built in trees, and usually positioned so that a clear flight path exists to at least one side of the nest as well as providing excellent visibility, often with an unobstructed view of water. Nest trees may be in woodlands, woodland edges, or open areas, and are frequently the dominant or co-dominant trees in the area (Green, 1985). Nests on cliffs and rock pinnacles have been reported in parts of the U.S.; nests on manmade structures are rare.

Water is also an important element of the winter habitat, with eagles usually frequenting lakes and major river systems. Wintering bald eagles also use habitats with little or no open water, if rabbits, carrion, or other food items are regularly available (Green, 1985). Winter roosting sites may often be used by several eagles.

### 2.10.3 Range

The bald eagle ranges throughout North America. Two subspecies are currently recognized based on size and weight: the northern bald eagle (*H.l. alascanus*) and the southern bald eagle (*H.l. leucocephalus*), the former being larger and heavier than the latter. This delineation, however, is of questionable merit due to a continuous size gradient from north to south throughout the range; eagles in the central part of the U.S. are intermediate in size. The northern population nests from central Alaska and the Aleutian Islands, east through Canada, and in the northern states of the U.S. The southern population nests primarily in the estuarine areas of the Atlantic and Gulf coasts from New Jersey to Texas and the lower Mississippi Valley, northern California to Baja California (both coasts), Arizona and New Mexico (Snow, 1981). Wintering ranges of the two populations overlap. Many of the northern bald eagles migrate south for the winter and can even be found as far south as Texas.

The southern eagles tend to be more resident although there is some northward movement during the summer (Snow, 1981). The largest wintering group is in Alaska, where over 3,000 have congregated in the Chilkat Valley during the fall and winter months (Steenhof, 1978).

### 2.10.4 Distribution in Texas

The southern subspecies nests in Texas along the Gulf coast and on major inland lakes during the winter months, and migrates to more-northern latitudes during the summer. The 1999 bald eagle nesting survey identified 82 nesting territories Statewide, the southernmost being in Refugio, Goliad, Victoria, and Matagorda counties. Of these nesting territories, 64 were occupied and 47 nests fledged 73 young (Mitchell, 1999). The northern bald eagle nests in the northern U.S. and Canada during spring and summer, and migrates to the southern U.S., including Texas, during the fall and winter. Concentrations of wintering northern eagles are often found around the shores of reservoirs in Texas, with most wintering concentrations occurring in the eastern part of the State. In Texas, wintering bald

eagles have been observed as far south as Cameron County (Oberholser, 1974; Mabie, 1990). They are considered to be a rare permanent resident in the Coastal Bend (Rappole and Blacklock, 1985)

#### 2.10.5 Presence in the Project Area

No nests are known to occur in the project area, nor have any been reported from Nueces County, the nearest known nest being in Refugio County (Mitchell, 1999). The checklist of birds of Mustang Island State Park does not list the bald eagle (Pulich et al., 1985), while the checklist of birds of Padre Island National Seashore (PINS) lists the bald eagle as rare in winter (Southwest Parks and Monuments Association (SPMA), 1990). If the bald eagle should occur in the project area, it would be only as a rare migrant or post-nesting visitor.

#### 2.10.6 Effects of the Project

Given the infrequent occurrence of bald eagles in the general area, no adverse impacts to this species are anticipated as a result of the project.

### 2.11 WHOOPING CRANE

#### 2.11.1 Reasons for Status

The whooping crane (*Grus americana*) was Federally listed as endangered on 11 March 1967 (32 FR 4001). Critical Habitat has been designated in Aransas, Calhoun, and Refugio counties in Texas, and includes the Aransas National Wildlife Refuge (NWR). Two experimentally introduced flocks are listed as experimental nonessential populations; in Florida (FR, 22 January 1993) and New Mexico (62 FR 38932). The main factors for the decline of the whooping crane were loss of habitat to agriculture, human disturbance of nesting areas, uncontrolled hunting, and collisions with power lines (NatureServe, 2000). Biological factors, such as delayed sexual maturity and small clutch size prevent rapid population recovery. Drought during the breeding season presents serious hazards to this species (Campbell, 1995). Whooping cranes are vulnerable to loss of habitat along their long migration route (NatureServe, 2000), along which they are still subject to cataclysmic weather events, accidental shooting, collision with power lines, and predators. They are susceptible to avian tuberculosis, avian cholera and lead poisoning (Campbell, 1995). Exposure to disease is a special problem when large numbers of birds are concentrated in limited areas, as often happens during times of drought.

While in Texas, the main population is at risk from chemical spills along the GIWW, which passes through the center of their winter range (Campbell, 1995). The presence of contaminants in the food base is another potential problem on their wintering grounds (Oberholser, 1974), and a late season hurricane or other weather event could be disastrous to this concentrated population.

#### 2.11.2 Habitat

Nesting habitat in Canada is freshwater marshes and wet prairies (NatureServe, 2000), interspersed with numerous potholes and narrow-wooded ridges. Whooping cranes use a variety of

habitats during migration (Campbell, 1995). They feed on grain in croplands (Lewis, 1995), and large wetland areas are used for feeding and roosting. Riverine habitats, such as submerged sandbars, are often used for roosting. The principle winter habitat in Texas is brackish bays, marshes, and salt flats, although whooping cranes sometimes feed in upland sites characterized by oak mottes, grassland swales, and ponds on gently rolling sandy soils (Campbell, 1995).

Summer foods include large insect nymphs or larvae, frogs, rodents, small birds, minnows and berries. During the winter in Texas they eat a wide variety of plant and animal foods. Blue crabs, clams, and berries of Carolina wolfberry (*Lycium carolinianum*) predominate the diet. Foods taken at upland sites include acorns, snails, crayfish, and insects (Campbell, 1995).

### 2.11.3 Range

Whooping cranes were originally found throughout most of North America. In the nineteenth century, the main breeding area was from the Northwest Territories to the prairie provinces in Canada, and the northern prairie states to Illinois. A non-migratory flock existed in Louisiana, but is now extirpated. Whooping cranes wintered from Florida to New Jersey along the Atlantic Coast, along the Texas Gulf Coast, and in the high plateaus of central Mexico. They now breed in isolated, marshy areas of Wood Buffalo National Park, Northwest Territories, Canada. They winter primarily in the Aransas NWR and adjacent areas of the central Texas Gulf Coast (FWS, 1995). During migration they use various stopover areas in western Canada and the American Midwest.

Two experimental flocks have been established by incubating eggs and rearing the young in captivity before releasing them into the wild. Whoopers were introduced in Grays Lake NWR in Idaho in 1975; these birds winter at Bosque del Apache NWR in central New Mexico. This population is not successfully breeding and will become extirpated. Introduction of another flock to Kissimmee Prairie in Florida began in 1993. The Florida population will be non-migratory (NatureServe, 2000).

### 2.11.4 Distribution in Texas

The natural wild population of whooping cranes spends its winters at the Aransas NWR, Matagorda Island, Isla San Jose, portions of the Lamar Peninsula, and Welder Point on the east side of San Antonio Bay (NatureServe, 2000). The main stopover points in Texas for migrating birds are in the central and eastern panhandle (FWS, 1995).

### 2.11.5 Presence in the Project Area

Although the leeward side and interior of Padre Island could provide suitable winter habitat for whooping cranes, Nueces County is outside the migration range of the whooping crane (FWS, 1995). The whooping crane in South Texas is generally restricted to the Aransas NWR in Aransas, Refugio, and Calhoun counties. This species is unlikely to occur in the project area.

#### 2.11.6 Effects of the Project

Given the lack of sightings in the area and the birds' fidelity to its wintering grounds at the Aransas NWR, no effects to the whooping crane are expected from this project.

#### 2.12 NORTHERN APLOMADO FALCON

##### 2.12.1 Reasons for Status

The northern aplomado falcon (*Falco femoralis septentrionalis*) was proposed for endangered status on 20 May 1985 (50 FR 20810). The listing was published as final on 25 February 1986 and the rule became effective on 27 March 1986 (51 FR 6686). Although reasons for the decline of the aplomado falcon are not known (Hector, 1987), habitat degradation due to brush encroachment is probably the main factor in the disappearance of this bird from the U.S. (Hector, 1983). Overcollecting of the falcons and their eggs may have contributed to the decline on a local basis (Hector, 1983, 1987). The National Audubon Society (NAS) (comments published in the Federal Register, 51 FR 6686, 25 February 1986) identified the decline as being through the loss of open grassland habitat through overgrazing and other excessive range practices. Currently, the most serious threat is reproductive failure caused by continued use of organochlorine pesticides such as DDT and DDE in Latin America, which affect both the aplomado falcon and its prey species (Hector, 1983).

##### 2.12.2 Habitat

Typical habitat of this species is open country, especially savannah rangeland and open woodland, containing scattered mesquites (*Prosopis* spp.), yuccas (*Yucca* spp.), oaks (*Quercus* spp.), and acacias (*Acacia* spp.) (Hector, 1983; 51 FR 6686, 25 February 1986; AOU, 1998). Open terrain with scattered trees (for nesting and observation perches), relatively low ground cover (less concealment for prey), an abundance of small- to medium-sized birds, and nesting platforms (e.g., stick nests or large bromeliads), particularly in yuccas and mesquites, are the habitat requirements for this bird (Hector, 1981; FWS, 1995). The preferred habitat of the aplomado falcon in southern Texas was coastal prairie with widely scattered mesquites and yuccas (Hector, 1987).

##### 2.12.3 Range

The aplomado falcon is resident throughout much of Central and South America (AOU, 1998). Three subspecies are recognized: the northern aplomado falcon (*F.f. septentrionalis*) and two others *F.f. femoralis* and *F.f. pichincha*) (Hector, 1983). The subspecies *septentrionalis* historically occurred in southeastern Arizona, southern New Mexico, southern Texas, much of Mexico, the Pacific coast of Guatemala, and perhaps Nicaragua where it intergrades with *F.f. femoralis*. Highest nesting densities in the U.S. were formerly in New Mexico and Texas; today this bird is virtually absent from the U.S. (Homerstad, 1990) and nests regularly only in the coastal plains of eastern Mexico (Vera Cruz, Chiapas, Campeche and Tabasco) in the palm and oak savannah and is rarely seen outside this area (Hector, 1981, 1983).

#### 2.12.4 Distribution in Texas

In Texas, the northern aplomado falcon formerly ranged from Cameron County northward to San Patricio County, and west from Ector and Midland counties to El Paso County (Oberholser, 1974). Around the turn of the century, the southeast corner of Cameron County was an important nesting area for the aplomado falcon, with over 100 nests being recorded (Hector, 1983). Other breeding records in Texas have come from Hidalgo, Kenedy, Brooks, Pecos, Ector and Midland counties, with the last nesting pair recorded from Brooks County in 1941 (Oberholser, 1974). Until recently, the last confirmed nesting in the U.S. was near Deming, New Mexico in 1952 (FWS, 1995). Since 1985, reintroduction efforts have been underway at several sites in south Texas in order to reestablish populations in the U.S. Reintroduction sites have included the Laguna Atascosa NWR and the King Ranch. These birds are hatched in California, flown to Texas at age 3 to 4 weeks, reared in hack boxes, and fed periodically following fledging. In 1995, a pair of these released birds successfully nested on a transmission line pole near Brownsville. In 1996 this same pair nested in a nearby mesquite, but the female and young were subsequently killed by a great horned owl (*Bubo virginianus*) (Anonymous, 1996).

#### 2.12.5 Presence in the Project Area

No aplomado falcons were observed in the project area during PBS&J's field survey, and it is unlikely that this bird occurs there. Even if this species recovers sufficiently from its present decline and spreads into its former range, lack of suitable nesting habitat in the project area would preclude its occurrence there.

#### 2.12.6 Effects of the Project

Because this falcon is not expected at present to occur in the project area, no impacts are anticipated.

### 2.13 PIPING PLOVER

#### 2.13.1 Reasons for Status

The piping plover (*Charadrius melodus*) was Federally listed as endangered on 11 December 1985 for the Great Lakes watershed and was listed as threatened throughout the remainder of its range (50 FR 50726). The rule became effective on 10 January 1986. In 1986, an estimated 2,100 to 2,300 breeding pairs occurred in North America: 1,337 to 1,409 pairs in the northern Great Plains, 19 to 24 pairs in the Great Lakes, and 799 pairs along the Atlantic coast (Haig et al., 1987). Shorebird hunting during the early 1900s caused the first known major decline of piping plovers (Bent, 1929). Since then, loss or modification of habitat due to commercial, residential, and recreational developments, dune stabilization, damming and channelization of rivers (eliminating sandbars, encroachment of vegetation, and altering water flows), and wetland drainage have further contributed to the decline of the species (FWS, 1995). Additional threats include human disturbances through recreational use of habitat, and predation of eggs by feral pets (FWS, 1995).

### 2.13.2 Habitat

Piping plovers typically inhabit shorelines of oceans, rivers and inland lakes. Nest sites include sandy beaches, especially where scattered tufts of grass are present; sandbars; causeways; bare areas on dredge-created and natural alluvial islands in rivers; gravel pits along rivers; silty flats; and salt-encrusted bare areas of sand, gravel, or pebbly mud on interior alkali lakes and ponds. In the wintering grounds these birds utilize beaches, mud flats, sand flats, dunes, and offshore spoil islands (AOU, 1998; FWS, 1995). One of the most important wintering areas for this species, the Laguna Madre in Mexico, became unsuitable when its water level was stabilized for a fisheries lagoon. In Texas, an estimated 30% of wintering habitat had been lost over a 20-year period (50 FR 50726; 11 December 1985).

### 2.13.3 Range

The piping plover breeds on the northern Great Plains (Iowa, northwestern Minnesota, Montana, Nebraska, North and South Dakota, Alberta, Manitoba, and Saskatchewan), in the Great Lakes (Illinois, Indiana, Michigan, Minnesota, New York, Ohio, Pennsylvania, Wisconsin and Ontario), and along the Atlantic coast from Newfoundland to Virginia and (formerly) North Carolina. It winters on the Atlantic and Gulf of Mexico coasts from North Carolina to Mexico, including coastal Texas, and, less commonly, in the Bahamas and West Indies (AOU, 1998; 50 FR 50726, 11 December 1985). Migration occurs both through the interior of North America east of the Rocky Mountains (especially in the Mississippi Valley) and along the Atlantic coast (AOU, 1998). Little is known about the migration routes of this species.

### 2.13.4 Distribution in Texas

The piping plover begins arriving to its post-breeding and wintering grounds in Texas in mid- to late-July. Haig and Oring (1985, 1987) found that early in the post-breeding season, piping plovers frequented beaches, but later tended to inhabit ephemeral sand flats along the backside of barrier islands. Observations of wintering piping plovers in Alabama did not indicate a seasonal preference between habitats, but that wintering plovers spent more than 85% of their time on sand flats or mud flats each month (Johnson and Baldassarre, 1988). Along the Texas coast, a correlation appears to exist between tidal height and habitat selection, with piping plovers actively feeding on tidal flats during periods of low tides, and on the Gulf beaches during high tides (Eubanks, 1991; Zonick, et al., 1998; Drake et al., 2000). Winter distribution studies along the Atlantic and Gulf coasts found piping plovers usually occurring in small, unevenly distributed groups along the coast; however, the sites with largest concentrations of plovers consisted of expansive sand flats or mud flats with sandy beach in close proximity (Nicholls and Baldassarre, 1990). Piping plover concentrations in Texas occur in the following counties: Aransas, Brazoria, Calhoun, Cameron, Chambers, Galveston, Jefferson, Kleberg, Matagorda, Nueces, San Patricio and Willacy (FWS, 1988).

Several areas along the Texas coast have been identified by the FWS as essential wintering habitat for the piping plover. Essential wintering habitat for the piping plover provides the space and requisite resources necessary for the continued existence and growth of piping plover populations and consist of coastal beach, sand-flat and mud-flat habitats.

Critical Habitat has recently been designated in Texas by the FWS (66FR 36074-36078), some of which lies within the study area as follows: the northern tip of TX-3; TX-5; TX-6; and part of TX-7. The Mollie Beattie Habitat Community (MBHC) forms part of TX-6. Figure 3 presents the location of the channel in reference to potential impacted units TX-6 and TX-7.

#### 2.13.5 Presence in the Project Area

The piping plover is a regular migrant and winter resident along the lower Texas coast (Oberholser 1974; Haig and Oring, 1985, 1987; Haig and Plissner, 1993; TOS, 1995) and wintering birds have been reported along the length of the Texas coast. The checklist of birds of Mustang Island State Park lists the piping plover as a fairly common winter resident and a common migrant (Pulich et al., 1985).

PBS&J conducted a piping plover survey in the Corpus Christi Bay area between September 2000 and April 2001 (PBS&J, 2001). Two of the four study sites, the Gulf Intracoastal Waterway (GIWW) and Fish Pass, fall within the northern portion of the Packery Channel study area. The study sites were visited monthly. Altogether, 652 piping plovers were recorded at the GIWW study site in 185.6 hours of observation at a rate of 3.5 birds per hour. Many of these birds were undoubtedly seen on more than one occasion. The number of individuals at the GIWW site ranged from 27 in October 2000 to 182 in March 2001, while the number of birds encountered per hour ranged from 1.5 for October 2000 to 7.8 for March 2001. Thus, a minimum of 182 piping plovers utilized the GIWW study site during the 2000-2001 survey.

At the Fish Pass study site, 148 piping plovers were recorded during 122.8 hours of observation at a rate of 1.2 birds per hour. Apart from December 2000 when no piping plovers were recorded, the number of individuals ranged from 8 in November 2000 to 45 in March 2001, while the number of birds encountered per hour ranged from 0.6 for February 2001 to 3.4 for March 2001. Thus, at least 45 piping plovers utilized the Fish Pass study site. No surveys were conducted at the MBHC.

#### 2.13.6 Effects of the Project

Based on modeling prepared for this project, a slight decrease in tidal range of approximately 0.04 to 0.09 feet will occur in Critical Habitat unit TX-6 as a result of opening Packery Channel, possibly resulting in slightly more tidal flat exposure, thereby increasing available foraging habitat to a minor degree. The effect of this impact on the piping plover is expected to be negligible. The change in tidal amplitude in Critical Habitat units TX-3 and TX-5, further south of the project site but within the general study area, will be approximately 0.01 foot or less, which is expected to result in no effect on these Critical Habitat units.

Impacts from salinity, based on modeling of the project, are relatively minor. With the opening of Packery Channel, salinity in the Laguna Madre, and thus within Critical Habitat units in the study area, is expected to fluctuate a few parts per thousand in the vicinity of the inlet with much smaller changes further from the project for each of the three salinity conditions modeled. Changes in salinity are not expected to be sufficient to affect the availability of invertebrate forage for piping plovers. More



discussion regarding tidal amplitude and salinity modeling is found in Section 4.2.1 of the DEIS to which this appendix is attached.

Critical Habitat units TX-6 and TX-7 will also be impacted by dredging and dredged material placement in PAs that are entirely or partially within them. Approximately 0.3 acre of TX-6 and approximately 5.9 acres of TX-7 will be removed by the initial and maintenance dredging to reopen and maintain the channel (Figure 3). In addition, approximately 24.6 acres within Critical Habitat unit TX-7 will be subject to periodic nourishment with sand from initial and maintenance dredging and from the sand bypass system. The 24.6 acres is the maximum area expected to be impacted during any single placement event and includes both north and south beach placement areas (PAs 4S and 4N) within Critical Habitat unit TX-7. PA 4N is proposed for maintenance placement only, while PA 4S will be used for both initial placement and maintenance material. Beach nourishment will serve to counteract the current trend of erosion along this portion of the Gulf beach. These events are anticipated to result in an approximately annual disturbance that will likely cause any plovers using the area to disperse from the immediate vicinity to use other, more favorable habitats in the area.

The effects of dredging and dredged material placement on the piping plover are expected to be minimal. In studies along the Lower Laguna Madre, Drake et al. (2000) found that overall usage of relatively undisturbed beach habitats by wintering piping plovers, including foraging and roosting, was minimal (2.8%). Piping plovers were found only to use beach habitats when other preferred habitats were unavailable, such as when algal and sand flats were inundated. This is considered to be partly due to the prime availability of forage on tidal flats and partly due to the high level of disturbance on beach habitats (Drake et al., 2000). The beach habitat within TX-7, identified as J.P. Luby Surf Park, is managed by the City of Corpus Christi and is subject to regular disturbance, including vehicle access and recreational beach activities. Because of the abundance of algal flats and sand flats in the adjacent critical habitat areas, paired with the heavy recreational and vehicular use of the beach areas in TX-7, impacts to TX-7 from dredging and dredged material placement are considered to be minor.

FWS (1997), in consultation regarding a slightly earlier stage of the Packery Channel project, determined that the reopening of Packery Channel is unlikely to jeopardize the continued existence of the piping plover.

## 2.14 MOUNTAIN PLOVER

### 2.14.1 Reason for Status

The mountain plover (*Charadrius montanus*) was proposed for listing as a threatened species on 16 February 1999 (64 FR 7587). It appears to be declining rapidly. One study indicated recent population declines of 50% to 89%. The breeding distribution has also contracted, with both peripheral populations disappearing and core populations going from widely distributed to only locally present. Early declines were probably at least partly related to market hunting. Historically, many mountain plovers nested in prairie dog towns (NatureServe, 2000), which have declined 98% in landscape coverage since 1900 (Summers and Linder, 1978)

Conversion of shortgrass prairie to agricultural land, primarily for winter wheat, has destroyed nesting habitat, as has planting of taller grasses in native prairie. In the last 25 years, farms on the western Great Plains have become larger and different crops have become more popular. Many farmers now grow extensive crops of millet and sunflower, ironically partially for the birdseed market. Fields for these crops remain fallow until early May, after most mountain plovers have begun nesting, and many nests are destroyed by cultivation activities. The plovers are likely to reneest in these fields after planting, only to be forced to abandon all the nests when the crops become too tall for the birds to scan their surroundings for predators. This major shift in regional activity has created a reproductive sink for mountain plovers, and may explain the annual decline since 1966 (Knopf, 1996). Encroachment on native prairies by exotic species such as cheatgrass (*Bromus tectorum*), leafy spurge (*Euphorbia esula*), and knapweed (*Centaurea* spp.) may be a factor (NatureServe, 2000).

#### 2.14.2 Habitat

The mountain plover, which actually avoids mountains, was originally named Rocky Mountain plover because the first specimens were taken within sight of that range. Instead, upland shortgrass plains and level plateaus of the western U.S. are its preferred summer haunts (Oberholser, 1974). Nesting areas are characterized by very short vegetation, and significant areas of bare ground (typically >30%), and flat or gentle slopes (<12%). Areas of moist ground are generally avoided, even for foraging. Non-breeding birds prefer short-grass plains and fields, plowed fields, sandy deserts (NatureServe, 2000), and sod farms (Knopf, 1996). They are attracted to heavily grazed annual grasslands and recent burns. Typical winter habitat in Texas is coastal prairies, alkaline flats, plowed fields, and bermudagrass fields (Oberholser, 1974). Mountain plovers are highly gregarious. Outside the breeding season they forage and roost in loose flocks of changing composition. Flock size may exceed 1,000 on the southern Great Plains in late summer. Mountain plovers may be attracted to cattle, sheep, and prairie dogs (NatureServe, 2000).

#### 2.14.3 Range

The mountain plover's historical breeding range was northern Montana south to central New Mexico, western Texas, and western Oklahoma, with very low numbers in extreme southern Alberta and perhaps Saskatchewan. This species now breeds mainly in Colorado, Wyoming, and Montana. Recent sightings of birds in June and July in the vicinity of Saltillo, Nuevo Leon, may have been of breeding birds. The non-breeding range is central California, southern Arizona, and central and near-coastal Texas, south to southern Baja California and the northern mainland of Mexico to San Luis Potosi. The primary wintering grounds are now in the San Joaquin, Sacramento, and Imperial valleys of California (Knopf, 1996).

#### 2.14.4 Distribution in Texas

The mountain plover is a rare summer resident in the high grasslands of the Trans-Pecos and in the northwest Panhandle. It is a rare migrant east to Delta County in the north and the Colorado

River in central Texas. It is a rare to uncommon local winter resident on the coastal plains and inland from south Texas through the Edwards Plateau into the South Plains (TOS, 1995).

#### 2.14.5 Presence in the Project Area

While the mountain plover has been recorded from Nueces County (Oberholser, 1974), it is most likely to occur in the agricultural areas away from the seashore. The mountain plover appears as an uncommon migrant on the checklist for birds of the Corpus Christi area (Audubon Outdoor Club of Corpus Christi (AOCCC), 1994), but is absent from checklists for Mustang Island State Park (Pulich et al., 1985) and PINS (SPMA, 1990). It is not expected to occur in the project area due to lack of suitable habitat.

#### 2.14.6 Effects of the Project

The mountain plover is unlikely to occur in the project area and, thus, will not be impacted by the proposed project.

### 2.15 ESKIMO CURLEW

#### 2.15.1 Reason for Status

The Eskimo curlew (*Numenius borealis*) was federally listed as endangered on 2 June 1970. It may be extinct; if not, it exists only in perilously low numbers. Only about 70 individuals have been seen anywhere in the last 60 years, and the last confirmed sighting of an Eskimo curlew was in Nebraska in 1987 (FWS, 1990a)

Eskimo curlews were extremely abundant in the nineteenth century and were subject to tremendous pressures from market hunting, especially after the demise of the passenger pigeon. They were held in high esteem as a food item, described by some as "the finest eating of any of our birds." Their abundance and tameness made supplying the demand an easy matter, and they were sold in restaurants and markets from Halifax to Buenos Aires. A pair of hunters on Cape Cod reportedly shot 5,000 curlews during the 1872 flight (Gollop et al., 1986). Market hunting for the Eskimo curlew flourished between 1860 and 1890, and was most intense during the late 1870s and 1890s in response to dwindling supplies of passenger pigeons (Gill et al., 1998).

Hunting was not the sole reason for the decline of the Eskimo curlew, for some population declines were noted several years before market hunting likely had significant impacts (Gill et al., 1998). This species was undoubtedly affected by habitat changes also. Over the last 125 years, a significant reduction has occurred in the amount and quality of habitat available to these birds along their migration routes. Urbanization and industrialization have impacted habitats on the Texas coast. Most of the grasslands used for spring migration feeding in the interior of North America have been converted to cropland. Most of the grassland on the pampas of Argentina have been converted to other uses and wet-meadow foraging habitat on Caribbean islands has been filled for tourism development. Pesticides and

chemical contaminants are used widely in all but a few areas throughout the Eskimo curlew's range (FWS, 1990a).

Populations declined suddenly during the 1870s and by the 1890s they had effectively disappeared. Sightings during the first half of the twentieth century were very rare. Between 1945 and 1985, Eskimo curlews were reported in 23 different years, in numbers from 1 to 23 individuals (Gill et al., 1998)

The Eskimo curlew is a relatively long-lived bird with probably a low reproductive rate, and certainly a very long migration route on which it is exposed to a number of factors. Perhaps the most important of these factors, in conjunction with hunting pressures, was the conversion of native prairies to agriculture along its spring migratory route, along with the suppression of fires. These phenomena were related to the extinction of the Rocky Mountain grasshopper (*Melanoplus spretus*), whose localized population irruptions were important to migrating curlews.

The Eskimo curlew fed on various invertebrates, seeds and berries. Berries were the preferred food source during the boreal autumn before migration (Gill et al., 1998).

#### 2.15.2 Habitat

The breeding habitat of the Eskimo curlew was treeless arctic and subarctic tundra (Gill et al., 1998). Non-breeding birds used a variety of habitats, such as grasslands, pastures, plowed fields, and, less frequently, marshes and mud flats (AOU, 1998). They favored headlands and hills within a few kilometers of the sea, and burned-over prairies and marshes were particularly attractive during migration. They roosted on beaches along the coast, but were rarely found near water in the midwestern states (Gollop et al., 1986)

#### 2.15.3 Range

The Eskimo curlew was only known to have nested in a relatively small portion of treeless tundra in the Northwest Territories, Canada, but the nesting range may have extended across northern Alaska into Siberia. They wintered in southern South America, primarily Argentina. Their fall migration took them eastward across Canada to the northeastern U.S., then southward across the Atlantic to South America. In spring they traveled through Texas and the midwestern U.S. (Gill et al., 1998).

#### 2.15.4 Distribution in Texas

The Eskimo curlew was formerly extremely abundant on the prairies of Texas, particularly in the middle portion of the State. It occurred in immense flocks until about 1875 and was observable in small flocks until about 1900 (Oberholser, 1974). The few records in recent years are from Galveston Island (TOS, 1995).

#### 2.15.5 Presence in the Project Area

Although the Eskimo curlew was formerly common in the spring in the Coastal Bend (Rappole and Blacklock, 1985), it is not expected to occur in the project area due to its extreme rarity, if not total extinction, and the lack of recent local records.

#### 2.15.6 Effects of the Project

The Eskimo curlew is highly unlikely to be impacted by this project due to the low probability of its occurrence in the area.

#### 2.16 OCELOT

##### 2.16.1 Reasons for Status

The ocelot (*Leopardus pardalis*) is listed as endangered throughout its present range (FWS, 1995, 2000c). Habitat destruction and degradation due to brush-clearing has been the major cause for the population decline, but predator control activities and hunting have also contributed. In Central and South America, exploitation for the fur and pet trade is primarily responsible for population declines (NFWL, 1980; FWS, 1995).

##### 2.16.2 Habitat

The ocelot occupies a variety of habitats throughout its neotropical range including tropical and subtropical forests, riverine forests, swampy savannas, estuarine mangroves, rocky areas, and upland oak forests (NFWL, 1980; Tewes and Schmidly, 1987; Murray and Gardner, 1997). In Texas, however, ocelots inhabit dense, often thorny and impenetrable brush, mesquite-oak and oak forests, and partially cleared land (NFWL, 1980; Navarro, 1985). Tewes (1986) found honey mesquite, acacias, condalia (*Condalia* spp.), allthorn goatbush (*Castella texana*), granjeno, cenizo, and whitebrush (*Aloysia texana*) to be the dominant brush species of ocelot habitat in south Texas. Approximately 1.6% of the land area in south Texas now supports this type of habitat (Tewes and Everett, 1987).

Tewes and Everett (1987) classified ocelot habitat in Texas according to the amount of foliar canopy. Class A or optimal habitat was 95% canopy cover, Class B or suboptimal habitat was 75% to 95% canopy cover, and Class C, with 75% or less canopy cover, was considered inadequate. The most Critical Habitat component is probably dense cover near the ground (<3 ft in height) (Tewes, 1986).

The ocelot is primarily nocturnal, although some diurnal activity has been recorded (Navarro, 1985; Tewes, 1986; Tewes and Schmidly, 1987). Navarro (1985) found ocelots in Texas to have two peaks of activity, one at about midnight and the other at daybreak. Ocelots feed on small and medium-sized mammals such as woodrats (*Neotoma* spp.), rabbits (*Sylvilagus* spp.), young deer (*Odocoileus* spp.), nutria (*Myocastor coypus*), birds, reptiles, amphibians, fish, insects and, in Latin America, spider monkeys (*Ateles* sp.), coatis (*Nasua nasua*), and agoutis (*Agouti* sp.) (Hall and Dalquest, 1963; Guggisberg, 1975; Navarro, 1985; Tewes and Schmidly, 1987; Emmons, 1988).

While breeding occurs throughout the year in the tropics, it occurs primarily in the fall (September through November) in Texas, although births have also been recorded in April, June, July and August. Den sites are usually well hidden and include dense, thorny scrub, caves, hollows in trees or logs, and grass tussocks (Petrides et al., 1951; Navarro, 1985; Tewes, 1986; Laack and Rappole, 1986, 1987a; Tewes and Schmidly, 1987). Gestation is 70 to 80 days. Litter size ranges from two to four, with two being the most common. The mother provides extended parental care to the young because it takes time for them to become proficient at capturing prey. Males are believed to contribute little to direct parental care (Tewes, 1986). Ocelots in the wild become sexually mature at 16 to 18 months (Schauenberg, 1979), but in captivity, maturity may be reached in as little as 10 to 12 months.

Navarro (1985) found that the average home range (the area which an animal occupies during its normal daily activities) for three male ocelots in south Texas was 618 acres, and for one female was 519 acres. Similarly, Twedt and Rappole (1986) reported home ranges of 865 and 296 acres for two male ocelots on Yturria Ranch in Willacy and Kenedy counties. However, Tewes (1986), using a much larger database, found the average home range of south Texas ocelots to be 4,372 acres for males and 2,717 acres for females. The overall average for adults was 3,754 acres. Although male ocelots had larger territories than the females and generally covered an extensive area in a short period, females used the home range more intensively (Tewes, 1986; FWS, 1990b). Tewes (1986) also determined that home ranges expanded in the winter and contracted in the summer. Both Navarro (1985) and Tewes (1986) found little overlap in the home ranges of adjacent males, but quite a considerable intersexual spatial overlap in the home ranges. Tewes and Schmidly (1987) and Navarro (1985) also found that the home ranges were closely aligned with the amount of suitable available habitat. At Laguna Atascosa NWR, for example, an increase in the ocelot population has resulted in smaller home ranges, two ocelots occupying an area that had previously supported only one (Tewes, 1988). Some individuals there currently inhabit areas as small as 80 acres (Tewes, 1988).

#### 2.16.3 Range

Historically, the ocelot occurred in Arkansas, Arizona, southern California, and south through Central and South America to Peru, Uruguay and northern Argentina (Navarro, 1985). Today it ranges from Arizona and Texas through Central and South America to northern Argentina, but in reduced numbers (Tewes and Everett, 1987; Emmons, 1990; Murray and Gardner, 1997).

#### 2.16.4 Distribution in Texas

The ocelot once occurred in the eastern, central and southern portions of Texas but currently only exists in the extreme south of the State (Davis and Schmidly, 1994). As a first step to determining the status of the ocelot in Texas, a clearinghouse for ocelot (and jaguarundi) sightings was established in October 1981 to coordinate reception and filing of reports. A total of 1,572 questionnaires was mailed to trappers to obtain additional information; of these, 472 (30%) were returned and 87 (6%) contained positive responses (Tewes and Everett, 1987). From these results, it appears that two significant populations of ocelots exist in south Texas. One population inhabits parts of Hidalgo, Starr, Cameron, and Willacy counties, and the other, Jim Wells, Live Oak, McMullen and Atascosa counties.

Six or seven smaller populations may also occur. Based on studies of spatial patterns and densities of radio-collared ocelots, Tewes (1986) estimated that only 80 to 120 ocelots occur in Texas. Laack (1998) currently puts this number at 100. A population of approximately 30 to 40 ocelots occurs on the Laguna Atascosa NWR in Cameron County (Laack, 1998). One or two ocelots apparently occur at the Santa Ana NWR (Benn, 1997; Laack, 1998) and one pair of ocelots had territories near the Arroyo Colorado in Cameron County (Laack, 1998). Ocelots have been sighted at the NAS's Sabal Palm Grove Sanctuary (Homerstad, 1986); and at the Loma de Grulla complex north of Laguna Vista, at Moranco Blanco, and at Redhead Ridge (Tewes, 1987). Ocelot sightings have also been reported from the Lower Rio Grande Valley NWR. In addition, Laack and Rappole (1986, 1987a), Tewes (1987) and Homerstad (1987) have documented several other ocelot sightings in Cameron County. The closest ocelot population in Mexico is near San Fernando, approximately 100 miles south of the U.S.-Mexico border (Laack, 1998).

#### 2.16.5 Presence in the Project Area

Ocelots are highly unlikely to occur in the project area due to the lack of suitable brushy habitat.

#### 2.16.6 Effects of the Project

No impacts to the ocelot are expected from this project as it is unlikely to occur in the project area due to the lack of suitable brushy habitat.

### 2.17 JAGUARUNDI

#### 2.17.1 Reasons for Status

The jaguarundi (*Herpailurus yagouaroundi*) was listed by FWS as endangered on 14 June 1976 (41 FR 24064). Habitat loss and alteration due to brush-clearing activities, and human persecution are the main causes for the decline in jaguarundi populations (FWS, 1995).

#### 2.17.2 Habitat

Habitat requirements in Texas are similar to those for the ocelot: thick, dense thorny brushlands or chaparral. Approximately 1.6% of the land area in south Texas is this type of habitat (Tewes and Everett, 1987). The thickets do not have to be continuous but may be interspersed with clear areas. Jaguarundis possibly show a preference for habitat near streams (Goodwyn, 1970; Davis and Schmidly, 1994). In South America, habitat includes high mountain forests, tropical forests, swamp forests, savannahs, overgrown pastures, and thickets (NFWL, 1980; Tewes and Schmidly, 1987).

The most common plants occurring in habitats in the Rio Grande Valley where the jaguarundi is known to occur are huisache, blackbrush acacia, prairie baccharis (*Baccharis texana*), chillipiquin (*Capsicum annuum*), lotebush, allthorn goatbush, Texas persimmon (*Diospyros texana*), coyotillo (*Karwinskia humboldtiana*), common lantana (*Lantana horrida*), berlandier wolfberry (*Lycium berlandieri*), javelinabrush (*Microrhamnus ericoides*), Texas pricklypear (*Opuntia lindheimeri*), retama,

honey mesquite, cedar elm (*Ulmus crassifolia*), and lime pricklyash (*Zanthoxylum fagara*) (Goodwyn, 1970).

Jaguarundis have two distinct color phases, red and gray, although the latter phase has also been called blue. The phases are so distinct that at one time they were thought to be separate species, the red one being called *Felis eyra*. A third color phase, black, has also been reported, but apparently does not occur in Texas (Goodwyn, 1970).

Like the ocelot, the jaguarundi is primarily nocturnal, although some diurnal activity has been recorded. Jaguarundis are excellent climbers although they spend most of the time on the ground. Prey is largely birds, but bird eggs, rats, mice, rabbits, reptiles and fish are also taken (Goodwyn 1970; Tewes and Schmidly, 1987; Davis and Schmidly, 1994). Jaguarundis communicate by calls, of which 13 have been identified in captive animals. The largest repertoire occurs during the mating season (Hulley, 1976).

Little is known of jaguarundi reproduction in the wild. Den sites include dense thickets, hollow trees, spaces under fallen logs overgrown with vegetation, and ditches overgrown with shrubs (Tewes and Schmidly, 1987; Davis and Schmidly, 1994). Young have been born in March and August with possibly two litters per year. Usually 2 to 4 young comprise a litter, with litters being either all of one color phase or containing both the red and gray phases. Gestation (for captive jaguarundis) varies from 63 to 75 days (Goodwyn, 1970; Tewes and Schmidly, 1987; Davis and Schmidly, 1994).

#### 2.17.3 Range

The jaguarundi historically occurred in southeast Arizona, south Texas, and Central and South America as far south as northern Argentina. Today this cat has a similar distribution, but in much reduced numbers, although it probably no longer occurs in Arizona (Tewes and Schmidly, 1987). The presence of jaguarundis in Florida is likely the result of human introduction (Nowak and Paradiso, 1983).

Four North American subspecies are recognized, of which two occur in the U.S.: *H.y. cacomilli* from southern Texas to central Vera Cruz, Mexico, and *H.y. tolteca* from southern Arizona, along the Pacific coast of Mexico, and inland to the Mexican Plateau (Goodwyn, 1970; NFWL, 1980).

#### 2.17.4 Distribution in Texas

Tewes and Everett (1987) analyzed the records of a clearinghouse established in 1981 to coordinate reception and filing of reports of jaguarundis (and ocelots) in Texas. Many of the reports were solicited by sending out questionnaires to trappers. Jaguarundis were reported from central Texas and the upper Gulf coast as well as from south Texas. However, due especially to the lack of any tangible evidence such as road kills, most of the sightings in the first two areas are believed to have been of black feral house cats. Two dead jaguarundis were reported in Cameron County and one each in Willacy and Webb counties. Tewes (1987) and Tewes and Everett (1987) documented several other credible reports of jaguarundis in these three counties. One of these was of a road-killed male jaguarundi found near the junction of SH 4 and Farm-to-Market Road (FM) 511 (Kellers Corner) in Cameron County on 21 April

1986 (Tewes, 1987; Laack and Rappole, 1987b). While this was the last confirmed record of a jaguarundi in Texas (Laack, 1998), unconfirmed jaguarundi sightings in Hidalgo County include Bentsen Rio Grande State Park, Santa Ana NWR, Lower Rio Grande Valley NWR, Cimarron Country Club, Wimberley Ranch, and the Anacua Unit of the TPWD Las Palomas Wildlife Management Area (Prieto, 1990, 1991; Benn, 1997). Unconfirmed but reliable sightings of a jaguarundi occurred at the Sabal Palm Grove Sanctuary in Cameron County in 1988 (Anonymous, 1989). Recent jaguarundi sightings have been reported from the Santa Ana NWR for March 1998 (Santa Ana NWR data). Based upon sighting reports, personnel of the Santa Ana NWR suspect the presence of jaguarundis on the refuge (Benn, 1997).

Tewes and Everett (1987) concluded that until verifiable evidence of jaguarundis from central Texas and the upper Gulf coast was forthcoming, jaguarundi distribution in Texas should be considered as restricted to the Rio Grande Valley. The number of jaguarundis in Texas is unknown, but certainly less than that of ocelots.

#### 2.17.5 Presence in the Project Area

Jaguarundis are extremely unlikely to occur in the project area due to the lack of suitable brushy habitat and the lack of any known populations in the area.

#### 2.17.6 Effects of the Project

No impacts to the jaguarundi are expected from this project as it is unlikely to occur in the project area due to the lack of suitable brushy habitat and the lack of any known populations in the area.

### 2.18 WEST INDIAN MANATEE

#### 2.18.1 Reasons for Status

The West Indian manatee (*Trichechus manatus*) was listed as endangered on 2 June 1970 (35 FR 8495). The largest known human-related cause of manatee mortality in Florida is collisions with hulls and/or propellers of boats and ships. The second-largest human-related cause of mortality in Florida is entrapment in floodgates and navigation locks. Other known causes of human-related manatee mortality include poaching and vandalism, entrapment in shrimp nets and other fishing gear, entrapment in water pipes, and ingestion of marine debris (FWS, 1993). Hunting and fishing pressures were responsible for much of its original decline, as manatees were heavily hunted for meat, hides, and bones until they were nearly extirpated (FWS, 1995).

A prominent cause of natural mortality in some years in Florida is cold stress, and major die-offs associated with the outbreaks of red tide have occurred, where manatees appear to have died due to ingestion of filter-feeding tunicates that had accumulated the neurotoxin-producing dinoflagellates responsible for causing the red tide (FWS, 1993). The low reproductive rate and habitat loss make it difficult for manatee populations to recover.

[This page intentionally left blank.]

- Allard, M.W., M.M. Miyamoto, K.A. Bjorndal, A.B. Bolton, and B.W. Bowen. 1994. Support for natal homing in green turtles from mitochondrial DNA sequences. *Copeia* 1994:34-41.
- American Ornithologists' Union (AOU). 1998. Check-list of North American Birds. Seventh edition. Allen Press, Inc., Lawrence, Kansas. 829 pp.
- Anonymous. 1989. Update on jaguarundi sightings. *Horizons* 14(1):8.
- . 1996. Update: recovery of the aplomado falcon. Aplomado Falcon Restoration Report. Available on the Internet: <<http://www.peregrinefund.org/aplo96.html>> 28 July 1998.
- Audubon Outdoor Club of Corpus Christi (AOCCC). 1994. Checklist of the birds within a 40-mile radius of Corpus Christi, Texas. 6th edition. Audubon Outdoor Club of Corpus Christi, Corpus Christi, Texas.
- Bakeberg, C. 1977. Cactus Lexicon. Blandford Press, Ltd. Poole, Dorset, PH 15 ILL. (originally published in Germany, 1966).
- Balazs, G. 1980. Synopsis of biological data on the green turtle in the Hawaiian Islands. NOAA Technical Memorandum. NMFS-SWFC-7. 141 pp.
- Barrett, S. 1996. Disease threatens green sea turtles. *Endangered Species Bulletin* 21(2):8-9.
- Bartlett, R.D. and P.P. Bartlett. 1999. A field guide to Texas reptiles and amphibians. Gulf Publishing Company, Houston, Texas. 331 pp.
- Beaver, C. 2001. Center for Coastal Studies, Texas A&M University - Corpus Christi. Personal communication to Sam Copeland, PBS&J, 24 September 2001.
- Benn, S. 1997. Endangered feline population and habitat enhancement. Final Report, Federal Aid Grant No. W-125-R-8, Project No. 12. Texas Parks and Wildlife Department, Austin, Texas. 30 September 1997. 12 pp.
- Bent, A.C. 1929. Life histories of North American shorebirds. Pt. 2. U.S. Natl. Mus. Bull. No. 146.
- Britton, N.L. and J.N. Rose. 1963. The cactaceae, vol. 3. Dover Publications, Inc., New York.
- Brongersma, L.D. 1972. European Atlantic turtles. *Zool. Verh.* 121. 318 pp.
- Caillouet, C.W. Jr., C.T. Fontaine, S.A. Manzella-Tirpak, and D.J. Shaver. 1993. Survival of head-started Kemp's ridley sea turtles (*Lepidochelys kempii*) released into the Gulf of Mexico or adjacent bays. *Chelonian Conservation and Biology* 1(4):285-292.
- Campbell, L. 1995. Endangered and threatened animals of Texas, their life history and management. Texas Parks and Wildlife Department, Resource Protection Division, Endangered Resources Branch. Austin, Texas. 130 pp.
- Carr, A.F. 1952. Handbook of turtles: the turtles of the United States, Canada and Baja California. Comstock Publ. Assoc., Cornell Univ. Press, Ithaca, New York. 542 pp.

- Clapp, R. B., R. C. Banks, D. Morgan-Jacobs and W. Hoffman. 1982. Marine birds of the southeastern U.S. and Gulf of Mexico. Part I: Gaviiformes through Pelicaniformes. U.S. Fish and Wildlife Service, Biological Services Program, Washington, D.C. FWS/OBS-82/01. Washington, D.C.
- Correll, D.S. and M.C. Johnston. 1970. Manual of the vascular plants of Texas. The University of Texas at Dallas, Richardson, Texas. 1881 pp.
- Davis, W.B. and D.J. Schmidly. 1994. The mammals of Texas. Texas Parks and Wildlife Dept. Distributed by University of Texas Press, Austin, Texas. 338 pp.
- Dixon, J.R. 2000. Amphibians and reptiles of Texas. Second edition. Texas A&M University Press, College Station, Texas. 421 pp.
- Domning, D.P. and L.C. Hayek. 1986. Interspecific and intraspecific variation in manatees (*Sirenia: Trichechus*). *Marine Mammal Sci.* 2:87-144.
- Drake, K., K. Drake, and J. Thompson. 2000. The effects of dredge material on piping plovers and snowy plovers along the southern Laguna Madre of Texas. Final Report 1997-1999. Caesar Kleberg Wildlife Research Institute/Texas A&M University, Kingsville. 147 pp.
- Eckert, S.A. 1992. Bound for deepwater. *Natural History*, March 1992, pp. 28-35.
- Emmons, L. 1988. A field study of ocelots (*Felis pardalis*) in Peru. *Rev. Ecol. (Terre Vie)* 43:133-157.
- . 1990. Neotropical rainforest mammals: a field guide. University of Chicago Press, Chicago and London. 281 pp.
- Ernst, C.H. and R.W. Barbour. 1972. Turtles of the United States. University of Kentucky Press, Lexington. 347 pp.
- Eubanks, T.L., Jr. 1991. Piping Plover Recovery Team. Piping plover workshop. Presentation given at Corpus Christi State University, Corpus Christi, Texas. 30 May 1991.
- Fish and Wildlife Service (FWS), U.S. Department of the Interior. 1980. Recovery Plan for the Eastern Brown Pelican (*Pelecanus occidentalis carolinensis*). Prepared in cooperation with the Eastern Brown Pelican Recovery Team. 46 pp.
- . 1981. Endangered species assessments and surveys in Hidalgo and Willacy counties, Texas. Final report to USCE, Galveston by USFWS, Denver Wildlife Research Center. 84 pp.
- . 1984. Southeastern states Bald Eagle Recovery Plan. U.S. Fish and Wildlife Service, Atlanta, Georgia. 63 pp. + App. A-I.
- . 1987. Endangered, threatened, proposed, and candidate 1 species occurring in Texas. U.S. Fish and Wildlife Service, Section 7 Workshop, July, 1987.
- . 1988. Great Lakes and Northern Great Plains piping plover recovery plan. U.S. Fish and Wildlife Service, Twin Cities, MN. 160 pp.
- . 1990a. Have you seen an Eskimo curlew? U.S. Fish and Wildlife Service. Grand Island, Nebraska: August 1990.

- . 1990b. Listed cats of Texas and Arizona Recovery Plan (with emphasis on the ocelot). U.S. Fish and Wildlife Service, Albuquerque, New Mexico. 131 pp.
- . 1993. Draft Florida manatee recovery plan, second revision, prepared by the Florida manatee recovery team for the U.S. Fish and Wildlife Service, Atlanta, Georgia. 176 pp.
- . 1995. Threatened and endangered species of Texas. Austin, Texas. June 1995.
- . 1998. Sea turtles. June 1998. Available on the Internet: <<http://www.fws.gov>>
- . 2000a. Federally listed as threatened and endangered species of Texas. FWS, 28 March 2000.
- . 2000b. Threatened and Endangered Species System (TESS). Available on the Internet: <[http://ecos.fws.gov/webpage/webpage\\_usa\\_lists.html](http://ecos.fws.gov/webpage/webpage_usa_lists.html)>
- . 2000c. Texas colonial waterbird nesting census. Available on the Internet: <<http://ifw2es.fws.gov/clearlaketexas/texascoastalprogram/birddata.htm>>
- Fish and Wildlife Service and National Marine Fisheries Service (FWS and NMFS). 1992. Recovery plan for the Kemp's ridley sea turtle (*Lepidochelys kempii*). National Marine Fisheries Service, St. Petersburg, Florida. 40 pp.
- Fritts, T.H., A.B. Irvine, R.D. Jennings, L.A. Collum, W. Hoffman and M.A. McGehee. 1983. Turtles, birds, and mammals in the northern Gulf of Mexico and nearby Atlantic waters. U.S. Fish and Wildlife Service, Division of Biological Services, Washington, D.C. FWS/OBS-82/65. 455 pp.
- Gardner, S. and R. O'Brien. 1987. Black lace cactus (*Echinocereus reichenbachii* var. *albertii*) recovery plan. Prepared for U.S. Fish and Wildlife Service. Albuquerque, New Mexico.
- Gill, R.E. Jr.; P. Canevari; and E.H. Iversen. 1998. Eskimo curlew (*Numenius borealis*). In: A. Poole and F. Gill (editors), The Birds of North America, No. 347. The Birds of North America, Inc., Philadelphia, PA.
- Gollop, J.B., T.W. Barry, and E.H. Iversen. 1986. Eskimo curlew a vanishing species? Saskatchewan Natural History Society. Special Publication No. 17. Regina, Saskatchewan, Northern Prairie Wildlife Research Center Home Page. Available on the Internet: <<http://www.npwrs.usgs.gov/resource/othrdata/curlew/current.htm>> Version 16 July 1997.
- Goodwyn, F. 1970. Behavior, life history and present status of the jaguarundi, *Felis yagouaroundi* (Lacepede), in south Texas. M.S. thesis, Texas A&I University, Kingsville, Texas. 63 pp.
- Green, D. 1984. Long-distance movements of Galapagos green turtles. Journal of Herpetology 18:121-130.
- Green, N. 1985. The Bald Eagle. In: A.M. Enos and R.L. DiSilvestro (editors), Audubon wildlife report 1985. Pp. 508-531. National Audubon Society, New York.
- Guggisberg, C. 1975. Wild cats of the world. Taplinger Publ. Co., New York. 382 pp.
- Guzman, H.M. and R.W. Schreiber. 1987. Distribution and status of brown pelicans in Venezuela in 1983. Wilson Bull. 99(2):275-279.

- Haig, S., W. Harrison, R. Lock, L. Pfanmuller, E. Pike, M. Ryan and J. Sidle. 1987. Draft recovery plan for piping plovers *Charadrius melodus* of the Great Lakes and Northern Great Plains. 161 pp.
- Haig, S.M. and L.W. Oring. 1985. Distribution and status of the piping plover throughout the annual cycle. *J. Field Ornithol.* 56(4):334-345.
- . 1987. The piping plover. In: 1987 Audubon Wildlife Report. National Audubon Society, Academic Press, New York, pp. 508-519.
- Haig, S.M. and J.H. Plissner. 1993. Distribution and abundance of piping plovers: results and implications of the 1991 international census. *The Condor* 95:145-156.
- Hall, E.R. and W. Dalquest. 1963. The mammals of Veracruz. *Mus. Nat. Hist., Univ. Kansas Publ.*, Lawrence, Kansas. 362 pp.
- Hector, D.P. 1981. The habitat, diet, and foraging behavior of the aplomado falcon, *Falco femoralis* (Temminck). M.S. thesis, Oklahoma State University, Cooperative Wildlife Research Unit.
- . 1983. Status report on *Falco femoralis septentrionalis*. U.S. Fish and Wildlife Service, Office of Endangered Species, Albuquerque, New Mexico. 51 pp.
- . 1987. The decline of the aplomado falcon in the United States. *American Birds* 41(3):381-389.
- Hildebrand, H. 1963. Hallazgo del area de anidacion de la tortuga marina "lora" *Lepidochelys kempfi* (Garman) en la costa occidental del Golfo de Mexico. *Ciencia (Mexico)* 22:105-112.
- . 1982. A historical review of the status of sea turtle populations in the western Gulf of Mexico. In: K. Bjorndal (editor), *Biology and Conservation of Sea Turtles*. Pp. 447-453. Smithsonian Institution Press, Washington, D.C. 583 pp.
- . 1983. Random notes on sea turtles in the western Gulf of Mexico. In: D. Owens et al. (editors) *Proc. Western Gulf of Mexico Sea Turtle Workshop*, Texas A&M University, College Station, Texas. Pp. 34-40. TAMU-SG-84-105. 74 pp.
- . 1986. Personal communication to Derek Green, EH&A, January 16, 1986. Corpus Christi, Texas.
- . 1987. A reconnaissance of beaches and coastal waters from the border of Belize to the Mississippi River as habitats for marine turtles. Report prepared for National Marine Fisheries Service, Southeast Fisheries Center, Panama City Laboratory, Panama City, Florida. Purchase Order No. NA-84-CF-A-134. 63 pp.
- Hirth, H.F. 1997. Synopsis of the biological data on the green turtle *Chelonia mydas* (Linnaeus 1758). *Biological Report* 97 (1). U.S. Fish and Wildlife Service, Washington, D.C. 120 pp.
- Homerstad, G.E. 1986. Feline status study. Performance Report, Federal Aid Project No. W-103-R-15, Job No. 12. Texas Parks and Wildlife Department, Austin, Texas. 5 March 1986. 3 pp.
- . 1987. Endangered feline status study. Performance Report, Federal Aid Project No. W-103-R-17, Job No. 12. Texas Parks and Wildlife Department, Austin, Texas. 9 October 1987. 7 pp.
- . 1990. Aplomado falcon restoration. Final Report, Federal Aid Project No. W-125-R-1, Job No. 62. Texas Parks and Wildlife Department, Austin, Texas. 7 November 1990. 3 pp.

- Hughes, G.R. 1974. The sea turtles of Southeast Africa. II. The biology of the Tongaland loggerhead turtle *Caretta caretta* L. with comments on the leatherback turtle *Dermochelys coriacea* L. and the green turtle *Chelonia mydas* L. in the study region. South African Association for Marine Biological Research, Oceanographic Research Institute, Investigational Report No. 36. Durban, South Africa. 96 pp.
- Hulley, J.T. 1976. Maintenance and breeding of captive jaguarundis (*Felis yagouaroundi*) at Chester Zoo and Toronto. *Int. Zoo. Yearb.* 16:120-122.
- Iverson, J.B. 1986. A checklist with distribution maps of the turtles of the world. Paust Printing, Richmond, Indiana. 284 pp.
- Johnson, C.M. and G.A. Baldassarre. 1988. Aspects of the wintering ecology of piping plovers in coastal Alabama. *Wilson Bulletin* 100(2):214-223.
- King, K.A., D.R. Blankinship, E. Payne, A. Krynitsky and G. Hensler. 1985. Brown pelican populations and pollutants in Texas 1975-1981. *Wilson Bull.* 97(2):201-214.
- King, K.A., E.L. Flickinger, and H. H. Hildebrand. 1977. The decline of brown pelicans on the Louisiana and Texas Gulf coast. *Southwestern Naturalist* 21(4):417-431.
- Knopf, F.L. 1996. Mountain plover (*Charadrius montanus*). In: A. Poole and F. Gill (editors), *The Birds of North America*, No. 211. The Academy of Natural Sciences, Philadelphia, PA, and the American Ornithologists' Union, Washington, D.C.
- Laack, L. 1998. Laguna Atascosa National Wildlife Refuge. Personal communication to Derek Green, EH&A, 23 June 1998.
- Laack, L. and J.H. Rappole. 1986. Investigation into the basic ecology of the ocelot in south Texas. Final Report (October 1, 1985 - September 30, 1986), contract #14-16-0002-81-229. Caesar Kleberg Wildlife Research Institute, Texas A&I University, Kingsville, Texas. 12 pp.
- . 1987a. Investigation into the basic ecology of the ocelot in south Texas. Final Report (October 1, 1986 - September 30, 1987), contract #14-16-0002-81-229. Caesar Kleberg Wildlife Research Institute, Texas A&I University, Kingsville, Texas. 19 pp.
- . 1987b. History of the jaguarundi road-kill from Cameron County, Texas. Report to U.S. Fish and Wildlife Service, Albuquerque, New Mexico. 6 pp.
- Leary, T. 1957. A schooling of leatherback turtles, *Dermochelys coriacea coriacea*, on the Texas coast. *Copeia* 3:232.
- Lefebvre, L.W., et al. 1989. Distribution, status, and biogeography of the West Indian manatee. In: C.A. Woods (editor), *Biogeography of the West Indies*. Pp. 567-610. Sandhill Crane Press, Gainesville, Florida.
- Lewis, J.C. 1995. Whooping crane (*Grus americana*). In: A. Poole and F. Gill (editors), *The birds of North America*, No. 153. The Academy of Natural Sciences, Philadelphia, and the American Ornithologists Union, Washington, D.C.
- Lonard, R. 1987. The status of *Anthericum chandleri* (Liliaceae) and *Ambrosia cheiranthifolia* (Compositae) in the proposed Playa del Rio project area, Cameron County, Texas. Report to U.S. Army Corps of Engineers, Galveston, Texas. 12 pp.

- Lund, P.F. 1974. A survey of marine turtle nesting in the United States. U.S. Dept. Interior. Unpubl. MS.
- Mabie, D.W. 1986. Brown pelican study. Final Report, Federal Aid Project No. W-103-R-15, Job No. 41. Texas Parks and Wildlife Department, Austin, Texas. 20 January 1986. 12 pp.
- . 1988. Personal communication to Derek Green, EH&A, 23 May 1988. Texas Parks and Wildlife Department, Rockport, Texas.
- . 1990. Brown pelican restoration. Performance Report, Federal Aid Project No. W-125-R-1 and ESEC-6-1, Job No. 41. Texas Parks and Wildlife Department, Austin, Texas. 19 October 1990.
- Marquez, R. 1994. Synopsis of biological data on the Kemp's ridley turtle, *Lepidochelys kempi* (Garman, 1880). NOAA Technical Memorandum NMFS-SEFSC-343. 91 pp.
- Meylan, A.B., B.W. Bowen, and J.C. Avise. 1990. A genetic test of the natal homing versus social facilitation models for green turtle migration. *Science* 248:724-727.
- Meylan, A. 1982. Sea turtle migration -- evidence from tag returns. In: K. Bjorndal (editor), *Biology and Conservation of Sea Turtles*. Pp. 91-100. Smithsonian Institution Press, Washington, D.C. 583 pp.
- Meylan, A.B. and M. Donnelly. 1999. Status justification for listing the hawksbill turtle (*Eretmochelys imbricata*) as critically endangered on the 1996 IUCN red list of threatened animals. *Chelonian Conservation and Biology* 3(2):200-224.
- Mitchell, M.R. 1999. Bald eagle nest survey and management. Performance Report, Federal Aid Grant No. W-125-R-6, Project No. 30. Texas Parks and Wildlife Department, Austin, Texas. 31 August 1999.
- Mortimer, J.A. 1982. Feeding ecology of sea turtles. In: K. Bjorndal (editor), *Biology and Conservation of Sea Turtles*. Pp. 103-109. Smithsonian Institution Press, Washington, D.C. 583 pp.
- Murray, J.L. and G.L. Gardner. 1997. *Leopardus pardalis*. Mammalian Species No. 548. Pp. 1-10.
- Musick, J. 1979. The marine turtles of Virginia with notes on identification and natural history. Educational Series No. 24. Sea Grant Program, Virginia Institute of Marine Science, Gloucester Point, Virginia. 18 pp.
- National Fish and Wildlife Laboratory (NFWL). 1980. Selected vertebrate endangered species of the seacoast of the United States. U.S. Fish and Wildlife Service, Biological Services Program, Washington, D.C. FWS/OBS-80/01.
- National Marine Fisheries Service (NMFS). 1998. Endangered Species Act – Section 7 Consultation, Biological Opinion. Deepening of Galveston Bay Entrance Channel (Houston – Galveston Navigation Channel Project) Using a Hopper Dredge. National Marine Fisheries Service, Southeast Region, 7 December 1998. 47 pp.
- . 2000. Information on sea turtles. Available on the Internet: <<http://www.nmfs.noaa.gov/prot-res/species/turtles/kemps.html>> 5 October 2000.
- National Marine Fisheries Service and U.S. Fish and Wildlife Service (NMFS and FWS). 1991a. Recovery plan for U.S. population of Atlantic green turtle. National Marine Fisheries Service, Washington, D.C. 52 pp.

- . 1991b. Recovery plan for U.S. population of loggerhead turtle. National Marine Fisheries Service, Washington, D.C. 64 pp.
- . 1992. Recovery plan for leatherback turtles in the U.S. Caribbean, Atlantic, and Gulf of Mexico. National Marine Fisheries Service, Washington, D.C. 65 pp.
- . 1993. Recovery plan for hawksbill turtles in the U.S. Caribbean Sea, Atlantic Ocean, and Gulf of Mexico. National Marine Fisheries Service, St. Petersburg, Florida. 52 pp.
- National Research Council (NRC). 1990. Decline of the sea turtles: causes and prevention. National Academy Press. Washington, D.C. 259 pp.
- NatureServe: an online encyclopedia of life [web application]. 2000. Version 1.0. Arlington (VA): Association for Biodiversity Information. Available on the Internet: <<http://www.natureserve.org>> Accessed: 5 October 2000.
- Navarro, D. 1985. Status and distribution of the ocelot (*Felis pardalis*) in south Texas. M.S. thesis, Texas A&I University, Kingsville, Texas. 92 pp.
- Nicholls, J.L. and G.A. Baldassarre. 1990. Winter distribution of piping plovers along the Atlantic and Gulf coasts of the United States. *Wilson Bulletin* 102(3):400-412.
- Nowak, R. and J.L. Paradiso. 1983. Walker's mammals of the world. Vol. 2. John Hopkins Univ. Press, Baltimore. 1362 pp.
- Oberholser, H.C. 1974. The bird life of Texas. 2 vol. University of Texas Press, Austin. 1069 pp.
- O'Shea, T.J., and M.E. Ludlow. 1992. Florida manatee (*Trichechus manatus latirostris*). Pp. 190-200 in S.R. Humphrey (editor). Rare and endangered biota of Florida. Volume 1: Mammals. University Press of Florida, Gainesville, Florida. 392 pp.
- Palmer, R.S. (editor). 1962. Handbook of North American birds. Vol. 1: Loons through Flamingos. Yale University Press, Newhaven, Connecticut, 567 pp.
- PBS&J. 2001. Piping and snowy plover survey, Corpus Christi Ship Channel Project, Nueces County, Texas, September 2000 April 2001. Final Report, PBS&J Document No. 010163. July 2001.
- Petrides, G.A., B.O. Thomas and R.B. Davis. 1951. Breeding of the ocelot in Texas. *J. Mamm.* 32:116.
- Poole, J.M. and D.H. Riskind. 1987. Endangered, threatened, or protected native plants of Texas. Texas Parks and Wildlife Department, Austin, Texas.
- Poole, J.M., J. Singhurst, D. Hurlburt-Price, and W.R. Carr. 2000. A list of rare plants of Texas. TPWD/TNC, Austin, Texas. January 2000. 28 pp.
- Prieto, F.G. 1990. Endangered feline population and habitat enhancement. Performance Report, Federal Aid Project No. W-125-R-1 and ESEC 6-1, Job No. 12. Texas Parks and Wildlife Department, Austin, Texas. 29 October 1990. 8 pp.
- . 1991. Endangered feline population and habitat enhancement. Performance Report, Federal Aid Project No. W-125-R-2 and ESEC 6-2, Job. No. 12. Texas Parks and Wildlife Department, Austin, Texas. 8 November 1991.

- Pritchard, P.C.H. 1971. The leatherback or leathery turtle *Dermochelys coriacea*. IUCN Monograph No. 1. International Union for Conservation of Nature and Natural Resources, Morges, Switzerland. 39 pp.
- . 1977. Marine turtles of Micronesia. Chelonia Press, San Francisco, California. 83 pp.
- Pritchard, P.C.H. and R. Marquez. 1973. Kemp's ridley turtle or Atlantic ridley, *Lepidochelys kempi*. IUCN Monograph 2, Morges, Switzerland. 30 pp.
- Pulich, W.M. Jr.; T. Amos, L. Turnbull, S. Holt, and J. Wilds, compilers. 1985. Birds of Mustang Island. Texas Parks and Wildlife Department, Resources Management Section. Austin, Texas. PWD Brochure 4000-432. June 1985.
- Rappole, J.H. and G.W. Blacklock. 1985. Birds of the Texas Coastal Bend, abundance and distribution. Texas A&M University Press. College Station, Texas. 126 pp.
- Rebel, T.P. 1974. Sea turtles and the turtle industry of the West Indies, Florida, and the Gulf of Mexico. Rev. Ed. Univ. Miami Press, Coral Gables, Florida. 250 pp.
- Ross, J.P. 1982. Historical decline of loggerhead, ridley, and leatherback sea turtles. In: K. Bjorndal (editor), *Biology and Conservation of Sea Turtles*. Pp. 189-195. Smithsonian Institution Press, Washington, D.C. 583 pp.
- Salmon, M., R. Reiners, C. Lavin, and J. Wyneken. 1995. Behavior of loggerhead sea turtles on an urban beach. 1. Correlates of nest placement. *Journal of Herpetology* 29:560-567.
- Schauenberg, P. 1979. Sa majesta l'ocelot. *Musees Geneve* 20:2-6.
- Schwartz, F. 1976. Status of sea turtles, Cheloniidae and Dermochelidae, in North Carolina. Abstr. in Proceedings and abstracts from the 73rd meeting of the North Carolina Academy of Science, Inc., April 2-3, 1976, at the Univ. N. Carolina, Wilmington, N. Carolina. *J. Elisha Mitchell Sci. Soc.* 92(2):76-77.
- Shaver, D. 1991. Feeding ecology of wild and head-started Kemp's ridley sea turtles in south Texas waters. *Journal of Herpetology* 25(3):327-334.
- . 2000. Padre Island National Seashore, field station leader. Personal communication to Derek Green, PBS&J, 20 November 2000.
- Shiner, Moseley and Associates, Inc. 1997. Re-opening Packery Channel, conceptual phase, jetties, shoreline stabilization & dredging. Prepared for Naismith Engineering, Inc. January 1997. Corpus Christi, Texas.
- Snow, C. 1981. Southern bald eagle (*Haliaeetus leucocephalus leucocephalus*) and northern bald eagle (*Haliaeetus leucocephalus alascanus*). Habitat management series for endangered species, Report No. 5. Bureau of Land Management, Denver, Colorado. T-N-171. 58 pp.
- Southwest Parks and Monuments Association (SPMA). 1990. A checklist of the birds of Padre Island National Seashore. Southwest Parks and Monuments Association, Tucson, Arizona. 4M/SPMA/1990.
- Spotila, J.R., A.E. Dunham, A.J. Leslie, A.C. Steyermark, P.T. Plotkin, and F.V. Paladino. 1996. Worldwide population decline of *Dermochelys coriacea*: are leatherback turtles going extinct? *Chelonian Conservation and Biology* 2(2):209-222.

- Steenhof, K. 1978. Management of wintering bald eagles. U.S. Fish and Wildlife Service, Washington, D.C. FWS/OBS-78/79. 59 pp.
- Summers, C.A. and R.L. Linder. 1978. Food habits of the black-tailed prairie dog in western South Dakota. *Journal of Range Management* 31:134-6.
- Tewes, M. 1986. Ecological and behavioral correlates of ocelot spatial patterns. Ph.D. dissertation, Univ. of Idaho, Moscow, Idaho. 128 pp.
- . 1987. Potential effects of the Playa del Rio Project on the endangered ocelot and jaguarundi. Report to U.S. Army Corps of Engineers, Galveston, Texas. 21 June 1987. 31 pp.
- . 1988. Personal communication to Derek Green, EH&A, 26 April 1988. Caesar Kleberg Wildlife Research Institute, Texas A&I University, Kingsville, Texas.
- Tewes, M. and D. Everett. 1987. Status and distribution of the endangered ocelot and jaguarundi in Texas. In: S.D. Miller and D.D. Everett (editors), *Cats of the world: biology, conservation, and management*. Pp. 147-158. National Wildlife Federation, Washington, D.C. 501 pp.
- Tewes, M. and D. Schmidly. 1987. The neotropical felids: jaguar, ocelot, margay and jaguarundi. Contribution No. 286 of the Welder Wildlife Foundation. 82 pp.
- Texas Ornithological Society (TOS). 1995. Checklist of the birds of Texas, 3rd Edition. Capital Printing, Inc., Austin, Texas. 166 pp.
- Texas Parks and Wildlife Department (TPWD). 1997. Federally and state endangered slender rush-pea (*Hoffmannseggia tenella* - PWD LF W3000-019N (1/97).
- . 1999a. South Texas Ambrosia. Available on the internet: <[www.tpwd.state.tx.us/nature/engand/plants/ambrosia.htm](http://www.tpwd.state.tx.us/nature/engand/plants/ambrosia.htm)> Last updated 10 September 1999.
- . 1999b. Black Lace Cactus. Available on the internet: <[www.tpwd.state.tx.us/nature/engand/plants/blklcca.htm](http://www.tpwd.state.tx.us/nature/engand/plants/blklcca.htm)> Last updated 10 September 1999.
- . 1999c. Slender Rush Pea. Available on the internet: <[www.tpwd.state.tx.us/nature/engand/plants/rushpea.htm](http://www.tpwd.state.tx.us/nature/engand/plants/rushpea.htm)> Last updated 10 September 1999.
- . 2000. Nature; endangered and threatened species; leatherback sea turtle (*Dermochelys coriacea*). Available on the Internet: <<http://www.tpwd.state.tx.us/nature/engand/animals/leathback.html>>
- Turner, B.L. 1983. Status report of *Ambrosia cheiranthifolia* Gray. Prepared for U.S. Fish and Wildlife Service.
- Twedt, D.J. and J.H. Rappole. 1986. Study of the ocelot (*Felis pardalis*) on Yturria Ranch. Final Report. Caesar Kleberg Wildlife Research Institute, Texas A&I University, Kingsville, Texas. 15 pp.
- URS/Dames & Moore (URS). 2002. 100% design submittal, design documentation report. Packery Channel – project design, Corpus Christi, Texas. Prepared for the U.S. Army Corps of Engineers, Galveston District, Galveston, Texas. March 1.
- U.S. Army Corps of Engineers (USACE). 1999. Project study plan Packery Channel, Texas, feasibility study phase, version 3. August 1999.

U.S. Fish and Wildlife Service (FWS), Department of the Interior. 1997. Identical letters from Jamie Rappaport Clark, Director, FWS, to Senators Phil Gramm and Kay Bailey Hutchison and Congressman Solomon P. Ortiz, dated 26 November 1997.

Witzell, W.N. 1983. Synopsis of biological data on the hawksbill turtle *Eretmochelys imbricata* (Linnaeus, 1766). FAO Fisheries Synopsis No. 137. FIR/S137, SAST -- Hawksbill Turtle -- 5.31 (07) 017.01. Food and Agriculture Organization (FAO) of the United Nations, Rome, Italy. 78 pp.

Zonick, C., K. Drake, K. Drake, L. Elliot, and J. Thompson. 1998. The effects of dredged material on piping plovers (*Charadrius melodus*) and snowy plovers (*C. alexandrinus*) in the lower Laguna Madre of Texas. Final Report for the 1997/1998 season.